

# Weston Solutions, Inc. Suite 201 1090 King Georges Post Road Edison, New Jersey 08837-3703 732-585-4400 ◆ Fax 732-225-7037 www.westonsolutions.com

229189

## The Trusted Integrator for Sustainable Solutions

REMOVAL SUPPORT TEAM 2 EPA CONTRACT EP-W-06-072

October 19, 2012,

Mr. Mark Gallo, On-Scene Coordinator U.S. Environmental Protection Agency, Region II Removal Action Branch 2890 Woodbridge Avenue Edison, NJ 08837

EPA CONTRACT No.: EP-W-06-072

TDD No.: TO-0027-0093

**DOCUMENT CONTROL No.: RST 2-02-F-2157** 

SUBJECT: FINAL SITE-SPECIFIC UFP QUALITY ASSURANCE PROJECT PLAN-JEWETT WHITE LEAD SITE, STATEN ISLAND, RICHMOND COUNTY, NEW YORK

Dear Mr. Gallo.

Enclosed please find the Final Site-Specific Uniform Federal Policy (UFP) Quality Assurance Project Plan (QAPP) for the Removal Action to be conducted at the Jewett White Lead Site located at 2000-2012 Richmond Terrace in Staten Island, Richmond County, New York beginning on October 9, 2012. Environmental Protection Agency (EPA) On-scene coordinator (OSC) comments have been incorporated. If you have any questions or comments, please do not hesitate to contact me at (732) 585-4449.

Sincerely,

Weston Solutions, Inc.

Brittney Kelly

RST 2 Site Project Manager

Enclosure

cc.

TDD File No.: TO-0027-0093

## SITE-SPECIFIC UFP QUALITY ASSURANCE PROJECT PLAN JEWETT WHITE LEAD SITE 2000-2012 Richmond Terrace, Staten Island, Richmond County, New York, 10302

# **NON-TIME CRITICAL**

# Prepared By:

Removal Support Team 2 Weston Solutions, Inc. Northeast Division Edison, New Jersey 08837

DCN No.: RST 2-02-F-2157 Task Order No.: TO-0027-0093 EPA Contract No.: EP-W-06-072

# TABLE OF CONTENTS

CROSSWALK	]
QAPP Worksheet #1: Title and Approval Page	
QAPP Worksheet #2: QAPP Identifying Information	
QAPP Worksheet #3: Distribution List	6
QAPP Worksheet #4: Project Personnel Sign-Off Sheet	
QAPP Worksheet #5: Project Organizational Chart	8
QAPP Worksheet #6: Communication Pathways	
QAPP Worksheet #7: Personnel Responsibilities and Qualifications Table	10
QAPP Worksheet #8: Special Personnel Training Requirements Table	
QAPP Worksheet #9: Project Scoping Session Participants Sheet	
QAPP Worksheet #10: Problem Definition	
QAPP Worksheet #11: Project Quality Objectives/Systematic Planning Process Statemen	
QAPP Worksheet #12: Measurement Performance Criteria Table	
QAPP Worksheet #13: Secondary Data Criteria and Limitations Table	18
O A TOTAL STATE OF THE STATE OF	
QAPP Worksheet #14: Summary of Project Tasks	2
QAPP Worksheet #16: Project Schedule/Timeline Table	23
QAPP Worksheet #17: Sampling Design and Rationale	24
QAPP Worksheet #18: Sampling Locations and Methods/SOP Requirements Table	
QAPP Worksheet #19: Analytical SOP Requirements Table	
QAPP Worksheet #20: Field Quality Control Sample Summary Table	
QAPP Worksheet #21: Project Sampling SOP References Table	28
QAPP Worksheet #22: Field Equipment Calibration, Maintenance, Testing, and Inspection	
Table	
QAPP Worksheet #23: Analytical SOP References Table	30
QAPP Worksheet #24: Analytical Instrument Calibration Table	
QAPP Worksheet #25: Analytical Instrument and Equipment Maintenance, Testing, and	
Inspection Table	
QAPP Worksheet #26: Sample Handling System	33
QAPP Worksheet #27: Sample Custody Requirements	34
QAPP Worksheet #28: QC Samples Table	36
QAPP Worksheet #29: Project Documents and Records Table	39
QAPP Worksheet #30: Analytical Services Table	40
QAPP Worksheet #31: Planned Project Assessments Table	41
QAPP Worksheet #32: Assessment Findings and Corrective Action Responses	42
QAPP Worksheet #33: QA Management Reports Table	43
QAPP Worksheet #34: Verification (Step I) Process Table	44
QAPP Worksheet #35: Validation (Steps IIa and IIb) Process Table	46
QAPP Worksheet #36: Validation (Steps IIa and IIb) Summary Table	
QAPP Worksheet #37: Usability Assessment	49

## **ATTACHMENTS:**

ATTACHMENT A: Site Location Map

ATTACHMENT B: EPA/ERT SOP# 2001 – General Field Sampling Guidelines

EPA/ERT SOP# 2008 – General Air Sampling Guidelines EPA/ERT SOP# 2012 – Soil Sampling Guidelines NIOSH 7300 Method – Air Sampling for Metals

#### LIST OF ACRONYMS

bgs below ground surface

CLP Contract Laboratory Program

COC chain of custody

CRQL contract required quantitation limit

DCN Document Control Number

DI Deionized Water
DQI data quality indicator
DQO data quality objective
EDD electronic data deliverable
EPA Environmental Protection

EPA Environmental Protection Agency
ERT Environmental Response Team

ESAT Environmental Services Assistance Team

HASP Health and Safety Plan HSO Health and Safety Officer

ICP-AES inductively coupled plasma atomic emission spectroscopy

LCSS laboratory control system mg/kg milligrams per kilogram

MPC measurement performance criteria
MS/MSD matrix spike/matrix spike duplicate

NA not applicable

NIST National Institute of Standards and Technology
NJDEP New Jersey Department of Environmental Protection

OSC On-Scene Coordinator

OSHA Occupational Safety and Health Administration
OSWER Office of Solid Waste and Emergency Response

PARCCS Precision, Accuracy, Representativeness, Completeness, Comparability,

Sensitivity

ppm parts per million

PQL practical quantitation limit PQO project quality objective

QA quality assurance

QAO Quality Assurance Officer
QAPP Quality Assurance Project Plan
QA/QC quality assurance/quality control

QC quality control

RAS routine analytical service RPD relative percent difference

RSCC Regional Sample Control Coordinator

RST Removal Support Team

SEDD staged electronic data deliverable

SOP standard operating practice

SOW statement of work

# LIST OF ACRONYMS (Concluded)

SPM	Site Project Manager
SRM	standard reference materials
STR	sampling trip report
TAL	target ànalyte list
TBD	to be determined
TDD	<b>Technical Direction Document</b>
UFP	Uniform Federal Policy

#### **CROSSWALK**

The following table provides a "cross-walk" between the QAPP elements outlined in the Uniform Federal Policy for Quality Assurance Project Plans (UFP-QAPP Manual), the necessary information, and the location of the information within the text document and corresponding QAPP Worksheet. Any QAPP elements and required information that are not applicable to the project are circled.

QAPP	P Element(s) and Corresponding Section(s) of UFP-QAPP Manual	Required Information	Crosswalk to QAPP Section	Crosswalk to QAPP Worksheet No.
		Project Management and Objectives		
2.1	Title and Approval Page	- Title and Approval Page	Approval Page	· 1
2.2	Document Format and Table of Contents  2.2.1 Document Control Format  2.2.2 Document Control Numbering System  2.2.3 Table of Contents  2.2.4 QAPP Identifying Information	- Table of Contents - QAPP Identifying Information	TOC Approval Page	2
2.3	Distribution List and Project Personnel Sign-Off Sheet 2.3.1 Distribution List 2.3.2 Project Personnel Sign-Off Sheet	- Distribution List - Project Personnel Sign-Off Sheet	Approval Page	3 4
2.4	Project Organization 2.4.1 Project Organizational Chart 2.4.2 Communication Pathways 2.4.3 Personnel Responsibilities and Qualifications 2.4.4 Special Training Requirements and Certification	<ul> <li>Project Organizational Chart</li> <li>Communication         <ul> <li>Pathways</li> </ul> </li> <li>Personnel             Responsibilities and             Qualifications</li> <li>Special Personnel Training             Requirements</li> </ul>	2	5 6 7 8
2.5	Project Planning/Problem Definition 2.5.1 Project Planning (Scoping) 2.5.2 Problem Definition, Site History, and Background	<ul> <li>Project Planning Session         Documentation (including Data Needs tables)     </li> <li>Project Scoping Session         Participants Sheet     </li> <li>Problem Definition, Site         History, and Background     </li> <li>Site Maps (historical and present)</li> </ul>	.1	9 10
2.6	Project Quality Objectives and  Measurement Performance Criteria  2.6.1 Development of Project Quality Objectives Using the Systematic Planning Process  2.6.2 Measurement Performance Criteria	Site-Specific PQOs     Measurement     Performance Criteria	3	11 12
2.7	Secondary Data Evaluation	- Sources of Secondary Data and Information - Secondary Data Criteria and Limitations	1 2	13
2.8	Project Overview and Schedule 2.8.1 Project Overview 2.8.2 Project Schedule	- Summary of Project Tasks - Reference Limits and Evaluation - Project Schedule/Timeline	4	14 15 16

	_		Measurement/Data Acquisition	
3.1	-	g Tasks	- Sampling Design and 5	17
	3.1.1	Sampling Process Design and	Rationale	,
		Rationale	- Sample Location	
	3.1.2	Sampling Procedures and	Мар	18
		Requirements	- Sampling Locations and	1 .
		3.1.2.1 Sampling Collection	Methods/SOP Requirements	
		Procedures	- Analytical Methods/SOP	. 19
		3.1.2.2 Sample Containers,	Requirements	
		Volume, and Preservation	- Field Quality Control	20
		3.1.2.3 Equipment/Sample	Sample Summary	
		Containers Cleaning and	- Sampling SOPs	21 '
		Decontamination	- Project Sampling SOP	
		Procedures	References	
		3.1.2.4 Field Equipment	- Field Equipment	. 22
		Calibration, Maintenance,	Calibration, Maintenance,	
		Testing, and Inspection	Testing, and Inspection	
		Procedures	resung, and hispection	
		3.1.2.5 Supply Inspection and		
				•
		Acceptance Procedures		
*		3.1.2.6. Field		
		Documentation		
		` Procedures		
3.2	Analytic	cal Tasks	- Analytical SOPs 6	23
	3.2.1	Analytical SOPs	- Analytical SOP	
	3.2.2	Analytical Instrument Calibration	References	S
		Procedures	- Analytical Instrument	24
	3.2.3	Analytical Instrument and	Calibration	
		Equipment Maintenance,	- Analytical Instrument and	25
		Testing, and Inspection	Equipment Maintenance,	
		Procedures	Testing, and Inspection	
	3.2.4	Analytical Supply Inspection and		
		Acceptance Procedures		· ·
3.3	Sample	Collection Documentation,	- Sample Collection 7	27
).J	•	g, Tracking, and Custody	Documentation Handling,	21
	Procedu		Tracking, and Custody SOPs	
	3.3.1	Sample Collection Documentation	Sample Container	
		•	<u> </u>	
	3.3.2	Sample Handling and Tracking	Identification	
	222	System .	- Sample Handling Flow	
	3.3.3	Sample Custody	Diagram	-26
			- Example Chain-of-	
			Custody Form and Seal	
3.4		Control Samples	- QC Samples 5	28
	3.4.1	Sampling Quality Control Samples	- Screening/Confirmatory	,
	3.4.2	Analytical Quality Control Samples	Analysis Decision Tree	
3.5	Data Ma	nnagement Tasks	- Project Documents and 6	29
	3.5.1	Project Documentation and Records	Records	29
	3.5.2	Data Package Deliverables	- Analytical Services	30
	3.5.3	Data Reporting Formats	- Data Management SOPs	30
	3.5.4	Data Handling and Management	- Data Management SOPS	
			·	· ·
	3.5.5	Data Tracking and Control		1

	•	Assessment/Oversight		
4.1 Asses: 4.1.1 4.1.2	Planned Assessments Assessment Findings and Corrective Action Responses	<ul> <li>Assessments and Response         Actions</li> <li>Planned Project Assessments</li> <li>Audit Checklists</li> <li>Assessment Findings and         Corrective</li> <li>Action Responses</li> </ul>	. 8	31 32
4.2 QA M	anagement Reports	- QA Management Reports		
· · · · · · · · · · · · · · · · · · ·	Project Report	- Final Report(s)		33
	· · · · · · · · · · · · · · · · · · ·	Data Review		
5.1 Overv	iew ·		\	
5.2 Data I 5.2.1 5.2.2 5.2.3	Step I: Verification Step II: Validation 5.2.2.1 Step IIa Validation Activities 5.2.2.2 Step IIb Validation Activities Step III: Usability Assessment 5.2.3.1 Data Limitations and Actions from Usability Assessment	<ul> <li>Verification (Step I)         Process     </li> <li>Validation (Steps IIa and IIb)         Process     </li> <li>Validation (Steps IIa and IIb)         Summary     </li> <li>Usability Assessment</li> </ul>	9	34 35 36 37

## QAPP Worksheet #1: Title and Approval Page

Title: Final Site-Specific UFP Quality Assurance Pr	oject Plan
Site Name/Project Name: Jewett White Lead Site	
Site Location: Staten Island, New York	
Revision Number: 00	
Revision Date: Not Applicable	
Weston Solutions, Inc.	
Lead Organization	
Brittney Kelly, Weston Solutions, Inc.	
1090 King Georges Post Road, Suite 201	
Edison, NJ 08837	
Email: Brittney.Kelly@WestonSolutions.com	6
Preparer's Name and Organizational Affiliation	
19 October 2012	
Preparation Date (Day/Month/Year)	
	$\mathcal{L}$
Site Project Manager:	19/19/12
	Signature
Brittney Kelly/Weston Solutions, Inc.	
Printed Name/Organization/Date	
QA Officer/Technical Reviewer:	All alan interlin
QIT Officer/ Technical Reviewer.	Etwita Suban 10/22/12
Smita Sumbaly/Weston Solutions, Inc.	signature
Printed Name/Organization/Date	0
Trinted Ivanic, Of ganization, Date	
EPA, Region II On-Scene Coordinator (OSC):	Mark Dal 1. 10/20/12
	Signature
Mark Gallo/EPA, Region II	Signaturo
Printed Name/Organization/Date	
EPA, Region II Quality Assurance Officer (QAO):	
	Signature
Printed Name/Organization/Date	
Document Control Number: RST 2-02-2157	

#### QAPP Worksheet #2: QAPP Identifying Information

Site Name/Project Name: Jewett White Lead Site

Site Location: 2000-2012 Richmond Terrace, Staten Island, Richmond County, New York

Operable Unit: 00

Title: Site-Specific UFP QAPP

Revision Number: 00

Revision Date: Not Applicable

1. Identify guidance used to prepare QAPP:

Uniform Federal Policy for Quality Assurance Project Plans. Refer to EPA DESA and NIOSH Method 7300.

2. Identify regulatory program: EPA, Region II

3. Identify approval entity: EPA, Region II

4. Indicate whether the QAPP is a generic or a Site-specific QAPP.

5. List dates of scoping sessions that were held: September 28, 2012

6. List dates and titles of QAPP documents written for previous site work, if applicable:

Site Quality Assurance Project Plan – Jewett White Lead Company Site,

DCN: RST-2-F-0755, 10 December 2008.

Final Quality Assurance Project Plan - Jewett White Lead Company Site,

DCN: RST-2-F-1214, 15 December 2009.

Draft Quality Assurance Project Plan - Jewett White Lead Company Site,

DCN: RST-2-F-1398, 10 August 2010.

Draft Quality Assurance Project Plan – Jewett White Lead Company Site,

DCN: RST-2-F-1524, 10 January 2011.

- 7. List organizational partners (stakeholders) and connection with lead organization: None
- 8. List data users:

EPA, Region II (see Worksheet #4 for individuals)

9. If any required QAPP elements and required information are not applicable to the project, then provide an explanation for their exclusion below:

None excluded.

10. Document Control Number: RST 2-02-2157

## **QAPP** Worksheet #3: Distribution List

[List those entities to which copies of the approved QAPP, subsequent QAPP revisions, addenda, and amendments are sent]

QAPP Recipient	Title	Organization	Telephone Number	Fax Number	E-mail Address	Document Control Number
Mark Gallo	EPA, On-Scene Coordinator	EPA, Region II	(732) 906-6871	(732) 906-6182	gallo.mark@epamail.epa.gov	RST 2-02-2157
Brittney Kelly	Site Project Manager, RST 2	Weston Solutions, Inc., RST 2	(908) 565-2979	(732) 225-7037	Brittney Kelly@WestonSolutions.com	RST 2-02-2157
Timothy Benton	HSO, RST 2	Weston Solutions, Inc., RST 2	(732) 585-4425	(732)-225-7037	tim.benton@WestonSolutions.com	RST 2-02-2157
Smita Sumbaly	QA Officer, RST 2	Weston Solutions, Inc., RST 2	(732) 585-4410	(732) 225-7037	S.Sumbaly@WestonSolutions.com	RST 2-02-2157
Site TDD File	RST 2 Site TDD File	Weston Solutions, Inc., RST 2		_		•

# QAPP Worksheet #4: Project Personnel Sign-Off Sheet


[Copies of this form signed by key project personnel from each organization to indicate that they have read the applicable sections of the QAPP and will perform the tasks as described; add additional sheets as required. Ask each organization to forward signed sheets to the central project file.]

Organization: Weston Solutions, Inc.

Project Personnel	, Title	Telephone / Number	Signature	Date QAPP Read
Mark Gallo	EPA Region 2, On-Scene Coordinator	(732) 906-6871	Mah Ball	10/26/12
Brittney Kelly	Site Project Manager, RST 2	(908) 565-2979	78K2	10/18/12
Smita Sumbaly	QAO, RST 2	(732) 585-4410	surty lest	10/22/1
Timothy Benton	HSO, RST 2	(732) 585-4425	in tel	10/22/12

#### **QAPP Worksheet #5: Project Organizational Chart**

Identify reporting relationship between all organizations involved in the project, including the lead organization and all contractor and subcontractor organizations. Identify the organizations providing field sampling, on-site and off-site analysis, and data review sérvices, including the names and telephone numbers of all project managers, project team members, and/or project contacts for each organization.



#### Acronyms:

SPM: Site Project Manager HSO: Health & Safety Officer

## **QAPP** Worksheet #6: Communication Pathways

Communication Drivers	Responsible Entity	Name	Phone Number	Procedure
Point of contact with EPA OSC	Site Project Manager, Weston Solutions, Inc., RST 2	Brittney Kelly	(908) 565-2975	All technical, QA and decision- making matters in regard to the project (verbal, written or electronic)
Adjustments to QAPP	Site Project Manager, Weston Solutions, Inc., RST 2	Brittney Kelly	(908) 565-2975	QAPP approval dialogue
Health and Safety On-Site Meeting	Site Project Manager, Weston Solutions, Inc., RST 2	Brittney Kelly	(908) 565-2975	Explain Site hazards, personnel protective equipment, hospital location, etc.

EPA – U.S. Environmental Protection Agency HSO – Health and Safety Officer OSC – On-Scene Coordinator

QA – quality assurance QAPP – Quality Assurance Project Plan RST – Removal Support Team SPM – Site Project Manager

## QAPP Worksheet #7: Personnel Responsibilities and Qualifications Table

-	Name	Title	Organizational Affiliation	Responsibilities	Education and Experience Qualifications
	Mark Gallo	EPA On-Scene Coordinator	EPA, Region 2	All project coordination, direction and decision making.	NA
	Brittney Kelly	Site Project Manager, RST 2	Weston Solutions, Inc.	Implementing and executing the technical, QA and health and safety during sampling event and sample management.	3 years*

<sup>\*</sup>All RST 2 members, including subcontractor's resumes are in possession of RST 2 Program Manager, EPA Project Officer and Contracting officers.

NA = not applicable

## **QAPP** Worksheet #8: Special Personnel Training Requirements Table

Project Function	Specialized Training By Title or Description of Course	Training Provider	Training Date	Personnel / Groups Receiving Training	Personnel Titles / Organizational Affiliation	Location of Training Records / Certificates
QAPP Training	This training is presented to all RST 2 personnel to introduce the provisions, requirements, and responsibilities detailed in the UFP QAPP. The training presents the relationship between the site-specific QA Project Plans (QAPPs), SOPs, work plans, and the Generic QAPP. QAPP refresher training will be presented to all employees following a major QAPP revision.	Weston Solutions, Inc., QAO	As needed	All RST 2 field personnel upon initial employment and as refresher training	Weston Solutions, Inc.	Weston Solutions, Inc., EHS Database
Health and Safety Training	Health and safety training will be provided to ensure compliance with Occupational Safety and Health Administration (OSHA) as established in 29 CFR 1910.120.	Weston Solutions, Inc., HSO	Yearly at a minimum	All Employees upon initial		
Others	FORMS II Lite, Scribe, ICS 100 and 200, and Air Monitoring Equipment Trainings provided to all employees	Weston Solutions, Inc., QAO/Group Leader's	Upon initial employment and as needed	employment and as refresher training every year	Weston Solutions, Inc.	Weston Solutions, Inc., EHS Database
	Dangerous Goods Shipping	Weston Solutions, Inc., HSO	Every 2 years			

All team members are trained in the concepts and procedures in recognizing opportunities for continual improvement, and the approaches required to improve procedures while maintaining conformance with legal, technical, and contractual obligations.

<sup>\*</sup>All RST 2 members, including subcontractor's certifications are in possession of RST 2 HSO.

## **QAPP Worksheet #9: Project Scoping Session Participants Sheet**

Site Name/Project Name: Jewett White Lead Site

Site Location: 2000-2012, 2015 Richmond Terrace, Staten Island, New York

Operable Unit: 00

Date of Session: September 28, 2012

Scoping Session Purpose: To discuss questions, comments, and assumptions regarding

technical issues involved with the project.

Name	Title	Affiliation	Phone #	E-mail Address
Mark Gallo	EPA OSC	EPA, Region II	(732) 906-6871	Gallo.Mark@epamail.epa.gov
Brittney Kelly	Site Project Manager	Weston Solutions, Inc.	(908) 565-2979	Brittney.Kelly@WestonSolutions.com
Timothy Benton	Operations Officer	Weston Solutions, Inc.	(732) 585-4425	Tim.Benton@WestonSolutions.com

#### Comments/Decisions:

The soil and air sampling activities to be conducted as part of the Removal Action at the Jewett White Lead Site (the Site) will commence on October 10, 2012. As part of the Removal Action, Weston Solutions, Inc., Removal Support Team 2 (RST 2) is tasked with the collection of up to 150 post excavation soil samples, including OA/OC samples, from locations throughout the Site identified by the U.S. Environmental Protection Agency (EPA) On-Scene Coordinator (OSC). The soil samples will be screened on-site using an X-Ray Fluorescent (XRF) unit and 20 % will be submitted to the U.S. Environmental Protection Agency (EPA) Division of Environmental Science and Assessment (DESA) laboratory for confirmatory total lead analysis. In addition, will establish upwind and downwind air monitoring to monitor/sample the ambient air around the perimeter of the Site during Removal Action activities. Each day of the Removal Action, RST 2 personnel will set up to 5 air sampling locations for the purpose of total lead air sampling collection using NIOSH Method 7300 and set up 3 sampling locations (2 downwind, 1 upwind) for the purpose collecting real-time monitoring using DustTrack and AreaRae units. Station locations will be set up on the perimeter of the work area based on EPA approval and daily wind direction. Up to 150 air samples will be collected from around the perimeter of the Site during Removal Action activities. The air samples will be submitted to a Contract Laboratory Program (CLP) laboratory for total lead analysis.

**Action Items:** 

The CLP Analytical Request Form was submitted on October 1, 2012.

**Consensus Decisions:** 

The Removal Action is scheduled to begin on October 10, 2012 and last approximately 2 months.

## **OAPP Worksheet #10: Problem Definition**

#### PROBLEM DEFINITION

EPA received a request in June 2008 to evaluate the Site for a possible cleanup. The agency collected soil samples throughout the Site in December 2008. Elevated levels of lead were detected throughout most of the Site. Off-site samples were collected from four locations along Richmond Terrace next to the Site in order to determine if contamination had migrated from the Site. Evidence of surface runoff leaving the Site was apparent along Richmond Terrace near the bus stop in December 2008. Lead was detected in the off-site samples, although at lower concentrations than on the Site.

EPA collected soil samples in the Port Richmond Community during early June 2009 to determine if the lead found in soils at the Site has affected the surrounding neighborhood. A total of 248 soil samples were collected from the backyards of homes closest to the Site and from the grassy areas on sidewalks in a six-block area closest to the Site. Background samples were collected in other grassy sidewalk areas approximately one-quarter mile away from the Site.

Lead was found at an average concentration of 549 milligrams per kilogram (mg/kg) in the top soils of the backyards sampled. This level of lead is higher than the EPA screening level of 400 mg/kg for lead in residential high use bare soil areas. Lead was detected in the grassy areas sampled both in the background and in the area surrounding the Site. The lead levels seen in the grassy area closest to the site are comparable to the levels detected in the background area. The average concentration of lead in the six-block area closest to the site is 666 mg/kg, while the average concentration of lead seen in the background area is 788 mg/kg. Lead was found at much lower levels in the road grit collected from the street curb lines. The overall average lead found in the road grit collected from all areas is 177 mg/kg, while the one block area surrounding the site was 132 mg/kg.

EPA concluded that lead is present in surface soils in the residential backyards, and the average lead level is slightly higher than EPA screening level of 400 mg/kg for lead. The highest lead levels were detected in samples collected closest to homes and other structures (i.e., at roof drip lines). Lead levels in the background area are similar to the lead levels seen closer to the Site.

EPA further evaluated the lead in neighborhood soils to determine whether it was associated with the Site, by evaluating six lines of evidence: spatial distribution, background results, lead-based paint on homes, urban soil studies, correlation of other elements, and lead isotope ratio fingerprinting. In order to support conclusions regarding lead isotope ratio fingerprinting, EPA collected additional on- and off-site soil samples for lead isotope analysis in March 2010. All six lines of evidence supported the conclusion that the source of lead in the neighborhood soils was primarily from paint on homes and use of leaded gasoline, and not the migration of lead from the Site. Based on this conclusion, EPA will not be conducting a cleanup of neighborhood soils.

EPA has determined that an immediate cleanup is needed to address the potential for soil contamination to migrate offsite due to the current use of the Site.

#### **QAPP** Worksheet #10: Problem Definition (Concluded)

#### SITE HISTORY/CONDITIONS

The Site consists of an approximately one-acre parcel of land located at 2000-2012 Richmond Terrace, in the Borough of Staten Island, Richmond County, New York. White lead, a type of lead formerly used as an ingredient for lead paint, was manufactured on the site from 1839 until 1898. National Lead Industries purchased the business and subsequently operated at the location for several decades. A major fire destroyed the plant's main building and storage house in the 1920s. Between 1949 and 1990, various businesses operated at the location. By the late 1990s, there had been several fires at the Site, which eventually led to the clearing of any remaining structures and debris in 2000. Currently, the 2000 Richmond Terrace property is fenced and is being used by the property owner to store construction materials and equipment, while the 2012 Richmond Terrace property is used as an automotive storage area and associated offices by a towing company.

#### PROJECT DESCRIPTION

EPA along with the Emergency Rapid Response Services (ERRS) and RST 2 contractors will be conducting a Removal Action at the Site beginning on October 10, 2012. The scope of work includes addressing the removal of contaminated soils via excavation and off-site disposal, and backfill of excavated areas with clean fill. RST 2 will provide Removal Action support at the Site. Approximately 150 perimeter air samples will be taken at up to five locations which will be collected daily for total lead analysis. Fugitive-dust monitors and AreaRae units will be placed at upwind and downwnind stations. Approximately 150 post-excavation soil samples will be collected during excavation activities and will be screened on-site using an XRF unit and 20% will be submitted to the EPA DESA laboratory for confirmatory total lead analysis. RST 2 will also monitor all on-site activities by the ERRS contractors. Daily reports will be provided, summarizing all on-site activities as well as weather data and air monitoring data.

#### PROJECT DECISION STATEMENTS

RST 2 personnel will set up 5 air sampling locations (3 downwind, 2 upwind) for the purpose of total lead air sampling collection using NIOSH Method 7300 for the purpose collecting real-time particulate monitoring using dust track units. Station locations will be set up on the perimeter of the work area based on EPA approval and daily wind direction. The analytical results for metals will be compared against the Occupational Safety and Health Administration (OSHA) Permissible Exposure Limit (PEL), 0.015 mg/m³ time-weighted average (TWA) for an 8-hour workday. The fugitive dust (total particulate matter) results from the DustTrak 8520 will be compared to the sites dust action level of 0.030 mg/m³, 15 minute average over background level, with a maximum of 0.063 mg/m³, 15 minute average as stated in the site specific Community Air Monitoring Plan (CAMP). If concentrations of lead in air exceed applicable standards, measures will be taken to reduce the amount of dust being generated (i.e. dust suppression).

#### QAPP Worksheet # 11: Project Quality Objectives/Systematic Planning Process Statement

Overall project objectives include: Sampling will be conducted by RST 2 to monitor perimeter air quality and to identify/confirm the presence of lead contamination in on-site soil.

Who will use the data? Data will be used by EPA, Region II OSC.

What will the data be used for? Data from air sampling is to ensure that any dust particulates generated from on-site activities does not contain unsafe concentrations of total lead. Data from soil sampling will be used to determine if all the lead contaminated soil has been removed.

#### What types of data are needed?

Matrix: Air and Soil

Type of Data: Definitive data

Analytical Techniques: Off-site laboratory analyses

Parameters: Total lead and particulates

Type of sampling equipments: .8-um, 37 mm cartridges (metals), SKC Pumps and

DustTrack Units (particulates)

Access Agreement(s): Obtained by EPA, Region II OSC.

Sampling locations: Around the perimeter of the Site (air sampling locations) and on-

site.

How many data are needed? Approximately 150 cassettes for total lead analysis will be needed for air sampling (assuming the project will take eight weeks with four air samples per day). Approximately 150 post-excavation soil samples will be collected to be analyzed for total lead.

## How "good" does the data need to be in order to support the environmental decision?

A definitive data deliverable has been requested for air samples collected for total lead. Field duplicates and MS/MSD samples are not required for air samples. A definitive data deliverable has been requested for soil samples collected for total lead. Field duplicates and MS/MSD samples are required for soil and will be collected every 20 samples.

Where, when, and how should the data be collected/generated? The air and soil samples to be collected from the Site have been determined/approved by the EPA OSC. All samples will be collected utilizing methods outlined in the Standard Operating Procedures (SOPs). The Removal Action is scheduled to begin on October 10, 2012.

Who will collect and generate the data? The soil samples will be will be analyzed and validated by the EPA DESA laboratory. The total lead air samples will be analyzed by a CLP laboratory and validated by Environmental Services Assistance Team (ESAT) data validation personnel.

How will the data be reported? Data will be reported by the assigned laboratories (Preliminary, Electronics, and Hard Copy format). The Site Project Manager will provide a Sampling Trip Report, Status Reports, Maps/Figures, Analytical Report, and Data Validation Report to the EPA OSC.

How will the data be archived? Electronic data deliverables will be archived in the database.

## QAPP Worksheet #12: Measurement Performance Criteria Table Worksheet # 12A: Total Lead - Air

#### (UFP-QAPP Manual Section 2.6.2)

Complete this worksheet for each matrix, analytical group, and concentration level. Identify the data quality indicators (DQI), measurement performance criteria (MPC) and QC sample and/or activity used to assess the measurement performance for both the sampling and analytical measurement systems. Use additional worksheets if necessary. If MPC for specific DQI vary within an analytical parameter, *i.e.*, MPC are analyte-specific, then provide analyte-specific MPC on an additional worksheet.

Matrix	Α	Air			
Analytical Group	Т	Total Lead			
Concentration Level	I	CP-Low (mg/m <sup>3</sup> )			
Sampling Procedure <sup>1</sup>	Analytica Method/SO		Measurement Performance Criteria	QC Sample and/or Activity Used to Assess Measurement Performance	QC Sample Assesses Error for Sampling (S), Analytical (A) or both (S&A)
EPA ERT SOP# 2008	ISMO1.3	Precision (field)	NR	NR	S & A
		Accuracy (Field)	No analyte > LOD	Field Blank	S & A

<sup>&</sup>lt;sup>1</sup>Reference number from QAPP Worksheet #21.

NR - Not Required

Note: Field duplicate samples are not required for air filter samples.

<sup>&</sup>lt;sup>2</sup>Reference number from QAPP Worksheet #23.

# QAPP Worksheet #12: Measurement Performance Criteria Table (Concluded) Worksheet # 12B: Total Lead - Soil

Complete this worksheet for each matrix, analytical group, and concentration level. Identify the data quality indicators (DQI), measurement performance criteria (MPC) and QC sample and/or activity used to assess the measurement performance for both the sampling and analytical measurement systems. Use additional worksheets if necessary. If MPC for specific DQI vary within an analytical parameter, *i.e.*, MPC are analyte-specific, then provide analyte-specific MPC on an additional worksheet.

Matrix	Soil		. The second second		
Analytical Group	Total Lead				
Concentration Level	Low		<u> </u>	,	
Sampling Procedure <sup>2</sup>	Analytical Method/SOP	Data Quality Indicators (DQIs)	Measurement Performance Criteria	QC Sample and/or Activity Used to Assess Measurement Performance	QC Sample Assesses Error for Sampling (S), Analytical (A) or both (S&A)
EPA ERT SOP# 2012	C-109	Precision	% RPD < 20( Aq), % RPD <25(Soil)	LÇS Duplicate	A
	`.	Accuracy	Limits: Average Recovery ± 20% aqueous, ± 25% Soil)	LCS	Α
		Accuracy	± 20% aqueous, ± 25% Soil)	Matrix spike	Α .
		Precision	< RL Except for Al, Fe, Ca, K, Mg and Na	Interference Check Sample(ICP/AES)	A
		Accuracy	< RL	Method Blank	A
		Precision	RPD < 20 %	Serial Dilution Test( ICP/AES)	<b>A</b> ,
		Accuracy	Range of 0.60-1.87 of the original response in the calibration blank	Internal Standards( ICP-MS)	А

<sup>&</sup>lt;sup>1</sup>Reference number from QAPP Worksheet #21.

<sup>&</sup>lt;sup>2</sup>Reference number from QAPP Worksheet #23.

## QAPP Worksheet #13: Secondary Data Criteria and Limitations Table

Any data needed for project implementation or decision making that are obtained from non-direct measurement sources such as computer databases, background information, technologies and methods, environmental indicator data, publications, photographs, topographical maps, literature files and historical data bases will be compared to the DQOs for the project to determine the acceptability of the data. Thus, for example, analytical data from historical surveys will be evaluated to determine whether they satisfy the validation criteria for the project and to determine whether sufficient data was provided to allow an appropriate validation to be done. If not, then a decision to conduct additional sampling for the site may be necessary.

Secondary Data	Data Source (Originating Organization, Report Title, and Date)	Data Generator(s) (Originating Org., Data Types, Data Generation/ Collection Dates)	How Data May Be Used (if deemed usable during data assessment stage)	Limitations on Data Use
Previous Investigation Sampling Results	Data Reports, Sampling Trip Reports delivered to EPA.	EPA, Region II. 31 December 2008 (Sampling Report Data Presentation), 10 January 2010 (Sampling Trip Report).	Data used to confirm soil and sediment contamination.	None.

#### **OAPP Worksheet #14: Summary of Project Tasks**

<u>Sampling Tasks</u>: RST 2 will provide Removal Action support at the Site. Approximately 150 perimeter air samples will be taken at up to five locations which will be collected daily for total lead analysis. Fugitive-dust monitors and AreaRae units will be placed at upwind and downwnind stations. Approximately 150 post-excavation soil samples will be collected during excavation activities and will be screened on-site using an XRF unit and 20 % will be submitted to the EPA DESA laboratory for confirmatory total lead analysis. RST 2 will also monitor all on-site activities by the ERRS contractors. Daily reports will be provided, summarizing all on-site activities as well as weather data and air monitoring data.

#### **Analysis Tasks:**

Total lead, air, CLP Method ISMO1.3 Total lead, soil, EPA DESA Method C-109

**Quality Control Tasks:** No QA/QC samples will be collected for the air samples for total lead. QA/QC samples will be collected for total lead soil samples and will include the collection of one duplicate and additional volume for MS/MSD at the ratio of 1 per 20 samples.

<u>Data Management Tasks:</u> Activities under this project will be reported in status and trip reports and other deliverables (e.g., analytical reports, final reports) described herein. Activities will also be summarized in appropriate format for inclusion in monthly and annual reports.

The following deliverables will be provided under this project:

<u>Trip Report:</u> A trip report will be prepared to provide a detailed accounting of what occurred during each sampling mobilization. The trip report will be prepared within two weeks of the last day of each sampling mobilization. Information will be provided on time of major events, dates, and personnel on-site (including affiliations).

<u>Maps/Figures:</u> Maps depicting site layout, contaminant source areas, and sample locations will be included in the trip report, as appropriate.

<u>Analytical Report:</u> An analytical report will be prepared for samples analyzed under this plan. Information regarding the analytical methods or procedures employed, sample results, QA/QC results, chain-of-custody documentation, laboratory correspondence, and raw data will be provided within this deliverable.

<u>Data Review</u>: A review of the data generated under this plan will be undertaken. The assessment of data acceptability or usability will be provided separately, or as part of the analytical report.

#### **Documentation and Records:**

All sample documents will be completed legibly, in ink. Any corrections or revisions will be made by lining through the incorrect entry and by initialing the error.

#### **QAPP Worksheet #14: Summary of Project Tasks (Continued)**

<u>Field Logbook</u>: The field logbook is essentially a descriptive notebook detailing site activities and observations so that an accurate account of field procedures can be reconstructed in the writer's absence. Field logbook will be bound and paginated. All entries will be dated and signed by the individuals making the entries, and should include (at a minimum) the following

- 1. Site name and project number
- 2. Name(s) of personnel on-site
- 3. Dates and times of all entries (military time preferred)
- 4. Descriptions of all site activities, site entry and exit times
- 5. Noteworthy events and discussions
- 6. Weather conditions
- 7. Site observations
- 8. Sample and sample location identification and description
- 9. Subcontractor information and names of on-site personnel
- 10. Date and time of sample collections, along with chain of custody information
- 11. Record of photographs
- 12. Site sketches

<u>Custody Seals</u>: Custody seals demonstrate that a sample container has not been tampered with or opened. The individual in possession of the sample(s) will sign and date the seal, affixing it in such a manner that the container cannot be opened without breaking the seal. The name of this individual, along with a description of the sample packaging, will be noted in the field logbook.

Assessment/Audit Tasks: No performance audit of field operations is anticipated at this time. If conducted, performance and system audit will be in accordance with the project plan.

**Data Review Tasks:** Data for all soil samples will be validated by the EPA's DESA laboratory. Data for all air samples will be validated by ESAT data validator personnel.

<sup>\*</sup> The description of the sample location will be noted in such a manner as to allow the reader to reproduce the location in the field at a later date.

## **QAPP Worksheet #15: Reference Limits and Evaluation Tables**

Matrix:

Air

Analytical Group:

Total Lead

**Concentration Level:** 

Low

Analyte	CAS Number	Project Quantitation Limit (ug/m³)	Analytical Method Reporting Limits (ug/m³)	Lab Achievable Reporting Limits (ug/filter)	EPA Lead PEL (mg/m³)	Site Action Level * (mg/m³)
Total Lead - CLP	7439-92-1	NS	٠ 1 ,	0.1	0.050	0.015

<sup>\*</sup>OSHA PEL for Lead, as specified in site-specific Community Air Monitoring Plan

## QAPP Worksheet #15b: Reference Limits and Evaluation Table

Matrix:

Soil

Analytical Group:

Total Lead

**Concentration Level:** 

Low

			EPA Screening	EPA Screening			, , , , , , , , , , , , , , , , , , , ,
		NYSDEC	Levels for Residential	Levels for Industrial	Project Quantitation		Laboratory ) Limits
Analyte	CAS Number	6NYCRR Part 375 (mg/kg)*	Soils (mg/kg)	Soils (mg/kg)	Limit (mg/kg)	MDLs (mg/kg)	RLs (mg/kg)
Total Lead	7439-92-1	63	400	800	,	5.06	50

<sup>\*</sup>New York Department of Environmental Conservation (NYSDEC), December 2006, 6 NYCRR Part 375 Environmental Remediation Programs, Subpart 375-6: Remedial Program Soil Cleanup Objectives (SCOs). Values listed from Table 375-6.8(a) for Unrestricted Use SCOs. The SCOs for unrestricted use were capped at a maximum value of 100 ppm. <a href="http://www.dec.ny.gov/regulations/2612.html">http://www.dec.ny.gov/regulations/2612.html</a>

# **QAPP** Worksheet #16: Project Schedule/Timeline Table

		•	Dates		
Activities	Organization	Anticipated Date(s) of Initiation	Anticipated Date of Completion	Deliverable	Deliverable Due Date
Preparation of QAPP	RST 2 Contractor Site Project Manager	Prior to sampling date	10/5/2012	QAPP	10/9/2012
Review of QAPP	RST 2 Contractor QAO and/or Group Leader	Prior to sampling date	10/8/2012	Approved QAPP	10/9/2012
Preparation of Health and Safety Plan	RST 2 Contractor Site Project Manager	Prior to sampling date	10/8/2012	HASP	10/9/2012
Procurement of Field Equipment	RST 2 Contractor Site Project Manager and/or Equipment Officer	Prior to sampling date	10/5/2012	NA	NA
Laboratory Request	RST 2 Contractor Site Project Manager and/or QAO	Prior to sampling date	10/1/2012	CLP Request Form	NA
Field Reconnaissance/Access	RST 2 Contractor Site Project Manager; or EPA, Region II OSC	Prior to sampling date	10/9/2012	Access Agreement(s)	NA
Collection of Field Samples	RST 2 Contractor Site Project Manager	TBĎ	TBD	TBD	TBD
Laboratory Electronic Data Received	EPA DESA and CLP Laboratories	TBD	TBD	Preliminary Data	TBD
Laboratory Package Received	EPA DESA and CLP Laboratories	TBD	<u></u>	•	. <del></del>
Validation of Laboratory Results	EPA DESA and CLP Laboratories	TBD	TBD	Validated Report	TBD
Data Evaluation/ Preparation of Final Report	RST 2 Contractor Site Project Manager	TBD	TBD	Final Report	TBD

## QAPP Worksheet #17: Sampling Design and Rationale

The Removal Action at the Site is expected to begin on October 10, 2012 and will be completed in approximately eight weeks. Approximately 150 perimeter air samples will be collected at approximately five locations which will be collected daily for total lead analysis through a CLP laboratory. Fugitive-dust monitors and AreaRaes will be placed at the upwind and downwind stations. Approximately 150 post-excavation soil samples will be collected during excavation activities. Samples will be analyzed for total lead through the EPA DESA laboratory, via method C-109.

The following laboratories will provide the analyses indicated:

Lab Name/Location	Sample Type	Parameters
Chemtech Consulting Group (CLP Lab)  284 Sheffield Street  Mountainside, NJ 07092	Air	Total Lead
EPA DESA Laboratory 2890 Woodbridge Ave. Bldg. 209, MS-230 Edison, NJ 08837	Soil	Total Lead

Refer to Worksheet #20 for QA/QC samples, sampling methods and SOP.

## QAPP Worksheet #18: Sampling Locations and Methods/SOP Requirements Table

Matrix	Sampling Location(s)	Units	Analytical Group(s)	Concentration Level	No. of Samples (identify field duplicates)	Sampling SOP Reference	Rationale for Sampling Location
Air	150	μg/m³	Total Lead	Low	150	EPA ERT SOP #: 2119	Perimeter of work Site and determined by the OSC
Soil	150	mg/kg	Total lead	Low	150	EPA ERT SOP #: 2001, 2012	Site Contamination Investigation

The website for EPA-ERT SOPs is: <a href="http://www.ert.org/mainContent.asp?section=Products&subsection=List">http://www.ert.org/mainContent.asp?section=Products&subsection=List</a>

# QAPP Worksheet #19: Analytical SOP Requirements Table

Matrix	Number of Samples	Analytical Group [Lab Assignment]	Concentration Level	Analytical and Preparation Method/SOP Reference	Sample Volume	Containers (number, size, and type)	Preservation Requirements	Maximum Holding Time (preparation/ analysis)
Air	150	Total lead	Low	ISMO1.3	Est. 960 Liters	0.8 um, 37 mm Cartridge	NA	30 days
Soil	150	Total lead	Low	C-109	(1) 2 oz. glass jar with Teflon lined cap	(1) 2 oz. glass wide-mouth short jars with Teflon lined cap. <sup>2</sup>	Cool – 4°C	6 months

# QAPP Worksheet #20: Field Quality Control Sample Summary Table

Matrix	Analytical Group	Concentration Level	Analytical and Preparation SOP Reference	No. of Sampling Locations	No. of Field Duplicate Pairs	No. of Extra Volume Laboratory QC (e.g., MS/MSD) Samples	No. of Rinsate Blanks	No. of Lot. Blanks	No of PE Samples	Total No. of Samples to Lab
Air	Total Lead	Low	ISMO1.3	150	NR	NR	· NR	1*	NR	150
Soil	Total lead	Low	C-109	150	l every 20 samples	l every 20 samples	NR	NR	NR	150

NR – not required
MS/MSD analysis not required for total lead analysis for air samples.
\* Two field blanks will be collected per batch.

# **QAPP** Worksheet #21: Project Sampling SOP References Table

Reference Number	Title, Revision Date and/or Number	Originating Organization	Equipment Type	Modified for Project Work? (Y/N)	Comments
SOP #2001	General Field Sampling Guidelines, Rev.0.0 August 1994	EPA/OSWER/ERT		N	<u>-</u>
SOP#2008	General Air Sampling Guidelines, Rev. 0.0 November 1994	EPA/OSWER/ERT	SKC 224-PCXR8	N	<del></del>
SOP#2012	Soil Sampling	EPA/OSWER/ERT	Styrene Scoops	N	- /
<u>NIOSH</u> <u>7300</u>	Air Sampling for Metals Guidelines, Rev. 0.0 October 1994	EPA/OSWER/ERT	DUSTRAC ^	N	1 vy

See Attachment B for EPA-ERT SOP # 2001, 2008, 2012 and NIOSH 7300

Note: The website for EPA-ERT SOPs is: <a href="https://www.ert.org/mainContent.asp?section=Products&subsection=List">www.ert.org/mainContent.asp?section=Products&subsection=List</a>

# QAPP Worksheet #22: Field Equipment Calibration, Maintenance, Testing, and Inspection Table

Field Equipment	Calibration Activity	Maintenance Activity	Testing/ Inspection Activity	Frequency	Acceptance Criteria	Corrective Action	Responsible Person	SOP Reference
SKC Pumps	Daily calibration	AC is primary power. Keep Internal trickle-charged battery with an approximate life of 8 hours.	Visually inspect the unit	Yearly	Follow equipment instruction	Replace batteries or replace unit if not working correctly	Equipment Vendor	
AreaRae Incl. PID	Calibrate with Zero Air; LEL: 2.5% (50% LEL) H <sub>2</sub> S: 10 ppm CO: 50 ppm PID: 100 ppm Isobutylene	Check/ replace battery/ Clean tip or bulb if necessary	Bump ~ Test	Prior to day's activities; anytime anomaly suspected	LEL: 48-52% LEL (2% LEL) H <sub>2</sub> S: 9-11 ppm (1 ppm) CO: 48-52 ppm (2 ppm) PID: 95-105 ppm Isobutylene (5 ppm)	Replace battery or Replace Unit	EPA Region 2	<del></del>
DustTrak 8520	Select auto 0/initiailize	Change Dust Filter	NA	Annual factory cleaning and calibration required	Follow equipment instruction	Factory Service and Calibration	Equipment Vendor	-

Trimble® GeoXTTM handheld

# QAPP Worksheet #23: Analytical SOP References Table

Reference Number	Title, Revision Date, and/or Number	Definitive or Screening Data	Analytical Group	Instrument	Organization Performing Analysis	Modified for Project Work? (Y/N)
C-109	Determination of Trace Elements in Aqueous Trace Metals in Aqueous, Soil/Sediment/Sludge- ICP-AES, Rev 2.0, 3/07	Definitive	Total Lead	ICP-AES	EPA DESA Laboratory 2890 Woodbridge Ave. Bldg. 209, MS-230 Edison, NJ 08837	N
ISMO1.3	NIOSH Manual of Analytical Methods, ISMO1.3	Definitive	Total Lead	ICP-AES	TBD (CLP Laboratory)	Ŋ

## **QAPP** Worksheet #24: Analytical Instrument Calibration Table

Inst	trument	Calibration Procedure	Frequency of Calibration	Acceptance Criteria	Corrective Action (CA)	Person Responsible for CA	SOP Reference
IC	CP-AES	See SOP C-109	See SOP C-109	See SOP C-109	See SOP C-109,	Assigned Lab Personnel	See SOP C-109
Mic	croscope	See NIOSH 7300	Initial calibration: daily or once every 24 hours and each time the instrument is set up.	As per instrument manufacture's recommended procedures.	Inspect the system, correct problem, re-calibrate, and re-analyze samples.	CLP Laboratory Microscope Technician	NIOSH 7300

## QAPP Worksheet #25: Analytical Instrument and Equipment Maintenance, Testing, and Inspection Table

Instrument/ Equipment	Maintenance Activity	Testing Activity	Inspection Activity	Frequency	Acceptance Criteria	Corrective Action	Responsible Person	SOP Reference <sup>1</sup>
See list of Instrument given in								
DESA Worksheet #24	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19	See LQMP, G-10, G-11, G-12, G-19
Microscope	See NIOSH 7300; as per instrument manufacturer's recommendations	See NIOSH 7300; as per instrument manufacturer's recommendations	See NIOSH 7300; as per instrument manufacturer's recommendations	Acceptable recalibration; See NIOSH 7300	Inspect the system, correct problem, re- calibrate and/or reanalyze samples.	Non-CLP Laboratory Microscope Technician	NIOSH 7300	Microscope

### QAPP Worksheet #26: Sample Handling System

SAMPLE COLLECTION, PACKAGING, AND SHIPMENT

Sample Collection (Personnel/Organization): RST 2 Site Project Manager, Weston Solutions, Inc., Region II

Sample Packaging (Personnel/Organization): RST 2 Site Project Manager and sampling team members, Weston Solutions, Inc., Region II

Coordination of Shipment (Personnel/Organization): RST 2 Site Project Manager, sampling team members, Weston Solutions, Inc., Region II

Type of Shipment/Carrier: FedEx delivery or hand-delivered

SAMPLE RECEIPT AND ANALYSIS

Sample Receipt (Personnel/Organization): EPA RAS and OSCAR/DESA Lab

Sample Custody and Storage (Personnel/Organization): EPA RAS and OSCAR/DESA Lab

Sample Preparation (Personnel/Organization): EPA RAS and OSCAR/DESA Lab

Sample Determinative Analysis (Personnel/Organization): EPA RAS and OSCAR/DESA Lab

SAMPLE ARCHIVING

Field Sample Storage (No. of days from sample collection): Samples to be shipped the day they are sampled and arrive at laboratory within 24 hours (1 day) of sample shipment

Sample Extract/Digestate Storage (No. of days from extraction/digestion): As per analytical methodology; see Worksheet #19

Biological Sample Storage (No. of days from sample collection): N/A

SAMPLE DISPOSAL

Personnel/Organization: Sample Technicians, EPA RAS and OSCAR/DESA Lab

Number of Days from Analysis: Until analysis and QA/QC checks are completed; as per analytical methodology; see Worksheet #19.

### QAPP Worksheet #27: Sample Custody Requirements

Sample Identification Procedures: Each sample will be labeled with the media type, a number that depicts a specific location, the date, and the sample number i.e. AA-004-101110-001. A field duplicate will have the next available sample number. The Lot Blank will be labeled LB, followed by the date. Specific media types are as follows:

Ambient Air - Sample Location - Date of collection-Sample Number (AA-004-01102011-001)

Field Sample Custody Procedures (sample collection, packaging, shipment, and delivery to laboratory): Each sample will be individually identified and labeled after collection, then sealed with custody seals and enclosed in a plastic cooler. The sample information will be recorded on chain-of custody (COC) forms, and the samples shipped to the appropriate laboratory via overnight delivery service or courier. Chain-of-custody records must be prepared in Scribe to accompany samples from the time of collection and throughout the shipping process. Each individual in possession of the samples must sign and date the sample COC Record. The chain-of-custody record will be considered completed upon receipt at the laboratory. A traffic report and chain-of-custody record will be maintained from the time the sample is taken to its final deposition. Every transfer of custody must be noted and signed for, and a copy of this record kept by each individual who has signed. When samples are not under direct control of the individual responsible for them, they must be stored in a locked container sealed with a custody seal. Specific information regarding custody of the samples projected to be collected on the weekend will be noted in the field logbook. The chain-of-custody record should include (at minimum) the following: 1) Sample identification number; 2) Sample information; 3) Sample location; 4) Sample date; 5) Sample Time; 6) Sample Type Matrix; 7) Sample Container Type; 8) Sample Analysis Requested; 9) Name(s) and signature(s) of sampler(s); and 10) Signature(s) of any individual(s) with custody of samples.

A separate chain-of-custody form must accompany each cooler for each daily shipment. The chain-of-custody form must address all samples in that cooler, but not address samples in any other cooler. This practice maintains the chain-of-custody for all samples in case of mis-shipment.

### QAPP Worksheet #27: Sample Custody Requirements (Concluded)

Laboratory Sample Custody Procedures (receipt of samples, archiving, and disposal): Within the laboratory, the person responsible for sample receipt must sign and date the COC form; examine all samples for possible shipping damage and improper sample preservation; note on the COC record that specific samples were damaged; notify sampling personnel as soon as possible so that appropriate samples may be regenerated; verify that sample holding times have not been exceeded; maintain laboratory COC documentation; and place the samples in the appropriate laboratory storage. At this time, no samples will be archived at the laboratory. Disposal of the samples will occur only after analyses and QA/QC checks are completed.

Note: Refer to Contract Laboratory Program Guidance for Field Samplers, EPA-540-R-07-06, July 2007 at: <a href="http://www.epa.gov/superfund/programs/clp/download/sampler/clp\_sampler\_guidance.pdf">http://www.epa.gov/superfund/programs/clp/download/sampler/clp\_sampler\_guidance.pdf</a>

# QAPP Worksheet #28: QC Samples Table DESA Worksheet #28A: Total Lead - Soil

### (UFP-QAPP Manual Section 3.4)

Soil

Matrix

Complete a separate worksheet for each sampling technique, analytical method/SOP, matrix, analytical group, and concentration level. If method/SOP QC acceptance limit exceed the measurement performance criteria, the data obtained may be unusable for making project decisions.

<u> </u>			-	the state of the s	•	-
Analytical Group	Total Lead					. '
Concentration Level	Low		1		•	
Sampling SOP	2012			· .	/	
Analytical Method/ SOP Reference	C-109 (Ref: EPA 200.7)			• •		
Sampler's Name	Brittney Kelly					
Field Sampling Organization	Weston Solutions, Inc., RST 2					
Analytical Organization	EPA DESA Laboratory			e e e e e e e e e e e e e e e e e e e		
No. of Sample Locations	150				. ,	
QC Sample:	Frequency/Number	Method/SOP QC Acceptance Limits	Corrective Action	Person(s) Responsible for Corrective Action	Data Quality Indicator (DQI)	Measurement Performance Criteria
Tuning/System	As per C-109	Pass all the	Check Instrument	Lab personnel	Sensitivity	Pass all the tune/stability criteria
Stability(ICP-MS)	713 per C 103	tune/stability criteria	Reanalyze, Retune	Lao personner	Sensitivity	ass an the tune/stability enteria
Initial Calibration Verification	Immediately following each calibration, after every 10 samples and at the end of each analytical run	90%-110%	Check Instrument, Reanalyze	Lab personnel	Accuracy	90%-110%
Continuing Calibration Check Standard (Alternate check standard)	Every 10 samples and at the end of each analytical run	80%-120%	Reanalyze, Qualify data	' Lab personnel	Accuracy	80%-120%
Initial Calibration Blank(ICB)	After ICV	< RL	Investigate source of contamination	Lab personnel	Sensitivity Contamination	< RL
Continuing Calibration Blank(CCB)	After every CCV	< RL	Investigate source of contamination	Lab personnel	Sensitivity Contamination	< RL
Low Level Check Standard	At Beginning and end of each analytical run	± 30% of the true value	Check Instrument, Re-calibrate	Lab personnel	Accuracy	± 30% of the true value

# QAPP Worksheet #28: QC Samples Table QAPP Worksheet # 28A: Total Lead - Soil (Concluded)

### (UFP-QAPP Manual Section 3.4)

Complete a separate worksheet for each sampling technique, analytical method/SOP, matrix, analytical group, and concentration level. If method/SOP QC acceptance limit exceed the measurement performance criteria, the data obtained may be unusable for making project decisions.

Matrix	Soil		•	•		
Analytical Group	Total Lead	·	•			
Concentration Level	Low		-	,		•
Sampling SOP	2012			•		
Analytical Method/ SOP Reference	C-109 (Ref: EPA 200.7)				<i>t</i>	
Sampler's Name	Brittney Kelly			•	1.	
Field Sampling Organization	Weston Solutions, Inc., RST 2					
Analytical Organization	EPA DESA Laboratory					
No. of Sample Locations	150				•	
QC Sample:	Frequency/Number	Method/SOP QC Acceptance Limits	Corrective Action	Person(s) Responsible for Corrective Action	Data Quality Indicator (DQI)	Measurement Performance Criteria
Interference Check Sample( ICP-200.7)	At Beginning and end of each analytical run	< RL Except Al, Fe, Ca, K, Mg and Na	As per C-109	Lab personnel	Precision	< RL Except Al ,Fe, Ca, K, Mg and Na
Method blank	1 per extraction batch of ≤ 20 samples	< RL	Investigate source of contamination	Lab personnel	Sensitivity Contamination	< RL
LCS/LFB	2 per extraction batch of ≤ 20 samples	Limits: Average Recovery ± 20% aqueous, ± 25% Soil) % RPD < 20( Aq), % RPD <25(Soil)	Qualify data	Lab personnel	Accuracy/ Precision	Limits: Average Recovery ± 20% aqueous, ± 25% Solids) % RPD < 20( Aq), % RPD <25(Soil
Laboratory Matrix spikes	1 per extraction batch of ≤ 20 samples	Limits ± 20% aqueous, ± 25% Soil)	- Qualify data	Lab personnel	Accuracy	Limits ± 20% aqueous, ± 25% Soil)
Serial Dilution Test (ICP-200.7)	Matrix spike sample	RPD < 20 %	Qualify data	Lab personnel	Precision	RPD < 20 %

# QAPP Worksheet #28: QC Samples Table QAPP Worksheet # 28B: Total Lead - Air

### (UFP-QAPP Manual Section 3.4)

Complete a separate worksheet for each sampling technique, analytical method/SOP, matrix, analytical group, and concentration level. If method/SOP QC acceptance limit exceed the measurement performance criteria, the data obtained may be unusable for making project decisions.

Matrix	Air
Analytical Group	Total Lead
Concentration Level	Low
Sampling SOP(s)	#2119
Analytical Method/SOP Reference	CLP ISMO1.3
Sampler's Name	Brittney Kelly
Field Sampling Organization	Weston Solutions, Inc.
Analytical Organization	CLP Laboratory
No. of Sample Locations	150

Lab QC Sample:	Frequency/Number	Method/SOP QC Acceptance Limits	Corrective Action	Person(s) Responsible for Corrective Action	Data Quality Indicator (DQI)	Measurement Performance Criteria
Field Blank	1 per week	No analyte>LOD	Suspend analysis until source recertified	Analyst	Accuracy	No analyte> LOD
Preparation Blank	1 per ≤ 20 samples	No constituent > CRQL	Suspend analysis until source rectified; redigest and reanalyze affected samples	EPA CLP RAS and Non- CLP Laboratory ICP- AES/ICP-MS Technicians	Accuracy	No constituent > CRQL
Interference Check Sample [ICP Analysis Only]	beginning, end and periodically during run (2 times every 8 hours)	Within ± 2 times CRQL of true value or ± 20% of true value, whichever is greater	Check calculations and instruments, reanalyze affected samples	EPA CLP RAS and Non- CLP Laboratory ICP- AES/ICP-MS Technicians	Sensitivity	Within ± 2 times CRQL of true value or ± 20% of true value, whichever is greater
Laboratory Control Sample	1 per ≤ 20 samples	Control limits established by EPA*	Suspend analysis until source rectified; redigest and reanalyze affected samples	EPA CLP RAS and Non- CLP Laboratory ICP- AES/ICP-MS Technicians	Accuracy	Control limits established by EPA*

<sup>\*</sup>except when the sample concentration is greater than 4 times the spike concentration, then disregard the recoveries; no data validation action taken

Note: Field duplicate sample not required for air samples and Matrix spike and lab duplicate analysis will not be performed for air samples.

<sup>\*\*</sup>Reference USEPA Region 2 SOP No. HW-2, Revision 13/Evaluation of Metals Data for CLP - (include absolute difference criteria)

<sup>\*\*</sup>except when the sample and/or duplicate concentration is less than 5 times the CRQL, then ± CRQL.

## QAPP Worksheet #29: Project Documents and Records Table

Sample Collection Documents and Records	Analysis Documents and Records	Data Assessment Documents and Records	Other
<ul> <li>Site and field logbooks</li> <li>COC forms</li> <li>Field Data Sheets</li> <li>GIS map for sampling locations</li> </ul>	Sample receipt logs     Internal and external COC forms     Equipment calibration logs     Sample preparation worksheets/logs     Sample analysis worksheets/run logs     Telephone/email logs     Corrective action documentation	<ul> <li>Data validation reports</li> <li>Field inspection checklist(s)</li> <li>Laboratory Audit checklist (if performed)</li> <li>Review forms for electronic entry of data into database</li> <li>Corrective action documentation</li> <li>Laboratory Final Data</li> </ul>	CLP Request Form Health and Safety Plan

## QAPP Worksheet #30: Analytical Services Table

Matrix	Analytical Group	Concentration Level	Analytical SOP	Data Package Turnaround Time	Laboratory/Organization (Name and Address, Contact Person and Telephone Number)	Backup Laboratory/Organization (Name and Address, Contact Person and Telephone Number)
Soil 2	Total lead	Low	C-109	48 hours	EPA DESA Laboratory 2890 Woodbridge Ave. Bldg. 209, MS-230 Edison, NJ 08837	NA
Air	Total lead	Low	ISMO1.3	72 hr	TBD (CLP Laboratory)	NA

## **QAPP** Worksheet #31: Planned Project Assessments Table

Assessment Type	Frequency	Internal or External	Organization Performing Assessment	Person(s) Responsible for Performing Assessment (Title and Organizational Affiliation)	Person(s) Responsible for Responding to Assessment Findings (Title and Organizational Affiliation)	Person(s) Responsible for Identifying and Implementing Corrective Actions (CA) (Title and Organizational Affiliation)	Person(s) Responsible for Monitoring Effectiveness of CA (Title and Organizational Affiliation)
DESA Laboratory	• .						
PT	Semiannually	External	NELAC	PT provider	Lab Personnel	Lab Personnel	Lab QA Officer
NELAC	Every two years	External	NELAC	Florida DOH	Lab QA Officer	Lab Personnel	Florida DOH
INTERNAL AUDIT	Monthly	Internally	DESA Lab	Lab QA Officer	Lab Personnel	Lab Personnel	Lab QA Officer
CLP Laboratory	)	• .					
Laboratory Technical Systems/ Performance Audits	Every year	External	Regulatory Agency	Regulatory Agency	EPA CLP RAS Laboratory	EPA CLP RAS Laboratory	EPA or other Regulatory Agency
Performance Evaluation Samples		External	Regulatory Agency	Regulatory Agency	EPA CLP RAS Laboratory	EPA CLP RAS Laboratory	EPA or other Regulatory Agency

### QAPP Worksheet #32: Assessment Findings and Corrective Action Responses

Assessment Type	Nature of Deficiencies Documentation	Individual(s) Notified of Findings (Name, Title, Organization)	Timeframe of Notification	Nature of Corrective Action Response Documentation	Individual(s) Receiving Corrective Action Response (Name, Title, Org.)	Timeframe for Response
Project Readiness Review	Checklist or logbook entry	RST 2 Site Project Manager, Weston Solutions, Inc.	Immediately to within 24 hours of review	Checklist or logbook entry	RST 2 Site Project Leader	Immediately to within 24 hours of review
Field Observations/ Deviations from Work Plan	Logbook	RST 2 Site Project Manager, Weston Solutions, Inc. and EPA OSC	Immediately to within 24 hours of deviation	Logbook	RST 2 Site Project Manager and EPA OSC	Immediately to within 24 hours of deviation
EPA DESA Laborat	ory	,				
Proficiency Testing	Letter with PT failure indicated	Lab QA Officer	30 days after the audit	Investigate the reason for the PT failure	Lab QA Officer	45 days after the CA report
NELAC	Audit Report with Non- conformance to	Lab Management	30 days after the audit	Investigate and have a corrective action plan for the deficiencies	Florida DOH	30 days after receiving notification
	QAPP, SOPs, NELAC+LQMP		81			
Internal	Audit Report with Non- conformance to QAPP, SOPs, NELAC Regulations	Lab Management	30 days after the audit	Investigate and have a corrective action plan for the deficiencies	Lab QA Officer	45 days after the CA report
CLP Laboratory	•		,	,		
Laboratory Technical Systems/ Performance Audits	Written Report	EPA CLP RAS and Non- CLP Laboratories	30 days	Letter	EPA CLP RAS	14 days

### QAPP Worksheet #33: QA Management Reports Table

Type of Report	Frequency (Daily, weekly, monthly, quarterly, annually, etc.)	Projected Delivery Date(s)	Person(s) Responsible for Report Preparation (Title and Organizational Affiliation)	Report Recipient(s) (Title and Organizational Affiliation)
EPA DESA Laboratory				
EPA DESA Laboratory Data (unvalidated)	As performed	Unknown	EPA Region II DESA Laboratory and CLP RAS Laboratory	RST 2 Site Project Manager, Weston Solutions, Inc.
EPA DESA Laboratory Data (validated)	As performed	Up to 60 days after receipt of unvalidated data	EPA Region II DESA Laboratory. Data Validator and EPA Region 2 ESAT Data Validator	EPA OSC, Region II and Site Project Manager, Weston Solutions, Inc.
Laboratory Technical Systems/ Performance Audits	As performed	Unknown	EPA or other Regulatory Agency	EPA Region II DESA Laboratory
CLP Laboratory		-		-
EPA CLP RAS Laboratory Data (preliminary)	As performed	Two weeks from the sampling date	EPA CLP RAS Laboratory	Adly Michael, RSCC, EPA Region II, RST 2 Data Validator and RST 2 Site Project Manager
EPA CLP RAS Laboratory Data (validated)	As performed	Up to 21 days after receipt of preliminary data	EPA Region II and RST 2 Data Validator	RST 2 Site Project Manager and OSC, EPA Region II
On-Site Field Inspection	As performed	7 calendar days after completion of the inspection	RST 2 Site Safety Officer	RST 2 Site Project Manager
Field Change Request	As required per field change	Three days after identification of need for field change	RST 2 Site Project Manager	EPA OSC
Final Report	As performed	2 weeks after receipt of EPA approval of data package	RST 2 Site Project Manager	EPA OSC

## QAPP Worksheet #34: Verification (Step I) Process Table

Verification Input	Description	Internal/ External	Responsible for Verification (Name, Organization)
Site/field logbooks	Field notes will be prepared daily by the RST 2 Site Project Manager and will be complete, appropriate, legible and pertinent. Upon completion of field work, logbooks will be placed in the project files.	I	RST 2 Site Project Manager
Chains of custody	COC forms will be reviewed against the samples packed in the specific cooler prior to shipment. The reviewer will initial the form. An original COC will be sent with the samples to the laboratory, while copies are retained for (1) the Sampling Trip Report and (2) the project files.	I	RST 2 Site Project Manager
Sampling Trip Reports	STRs will be prepared for each week of field sampling. Information in the STR will be reviewed against the COC forms, and potential discrepancies will be discussed with field personnel to verify locations, dates, etc.	I	RST 2 Site Project Manager
Laboratory analytical data package	Data packages will be reviewed/verified internally by the laboratory performing the work for completeness and technical accuracy prior to submittal.	Е	EPA DESA Laboratory, CLP RAS Laboratory
Laboratory analytical data package	Data packages will be reviewed as to content and sample information upon receipt by EPA.	I	ESAT Data Validation Personnel, EPA, Region II, DESA Data Validation Personnel
Final Sample Report	The project data results will be compiled in a sample report for the project. Entries will be reviewed/verified against hardcopy information.	I'	RST 2 Site Project Manager
EPA DESA Laboratory			
Chain of Custody	Chain-of-custody forms will be verified against the sample cooler they represent. Sample Acceptance Checklist is completed.	Internal	OSCAR Personnel
	The OSCAR staff supervisor utilizes the analyses request information and the external COC to review the accuracy and completeness of LIMS log-in entries, as reflected on the LIMS Sample Receipt Form Details can be found in Laboratory Quality Management Plan, SOP G-25		DESA LAB

## QAPP Worksheet #34: Verification (Step I) Process Table (Concluded)

Verification Input	Description	Internal/ External	Responsible for Verification (Name, Organization)
EPA DESA Laboratory			
Analytical data package/ Final Report	The procedures for data review:  1- Data reduction/review by Primary Analyst.  2- Review complete data package (raw data) by independent Peer Reviewer  3- The Sample Project Coordinator reviews the project documentation for completeness followed by a QA review by the QAO  4- Final review by Branch Chief/Section Chief prior to release, this review is to ensure completeness and general compliance with the objectives of the project. This final review typically does not include a review of raw data. Details can be found in Laboratory Quality Management Plan.	Internal	Primary Analyst, Peer Reviewer, Sample Project Coordinator, Quality Assurance Officer, Section Chief/ Branch Chief. DESA LAB

### QAPP Worksheet #35: Validation (Steps IIa and IIb) Process Table

Step Ha/Hb	Validation Input	Description	Responsible for Validation (Name, Organization)
IIa -	SOPs	Ensure that the sampling methods/procedures outlined in QAPP were followed, and that any deviations were noted/approved.	RST 2 Site Project Manager
IIb	SOPs	Determine potential impacts from noted/approved deviations, in regard to PQOs.	RST 2 Site Project Manager
EPA DESA La	iboratory \		
		Chain-of-custody forms will be verified against the sample cooler they represent. Sample Acceptance Checklist is completed.	OSCAR Personnel
	Chain of Custody	The OSCAR staff supervisor utilizes the analyses request information and the external COC to review the accuracy and completeness of LIMS log-in	DESA LAB
		entries, as reflected on the LIMS Sample Receipt Form  Details can be found in Laboratory Quality Management Plan, SOP G-25	
•	Analytical data package/ Final	The procedures for data review:	Primary Analyst, Peer Reviewer, Sample Project
,	Report	1- Data reduction/review by Primary Analyst.	Coordinator, Quality
		<ul> <li>2- Review complete data package (raw data) by independent Peer</li> <li>Reviewer</li> <li>3- The Sample Project Coordinator reviews the project documentation for</li> </ul>	Assurance Officer, Section Chief/ Branch Chief.
		completeness followed by a QA review by the QAO 4- Final review by Branch Chief/Section Chief prior to release, this review	DESA LAB
		is to ensure completeness and general compliance with the objectives of the project. This final review typically does not include a review of raw data.  Details can be found in Laboratory Quality Management Plan.	

### QAPP Worksheet #35: Validation (Steps IIa and IIb) Process Table (Concluded)

Step IIa/IIb	Validation Input	Description	Responsible for Validation (Name, Organization)			
CLP Laboratories						
IIa	Chains of custody	Examine COC forms against QAPP and laboratory contract requirements (e.g., analytical methods, sample identification, etc.).	ESAT Data Validation			
IIa	Laboratory data package	Examine packages against QAPP and laboratory contract requirements, and against COC forms (e.g., holding times, sample handling, analytical methods, sample identification, data qualifiers, QC samples, etc.).	ESAT Data Validation			
IIb	Laboratory data package	Determine potential impacts from noted/approved deviations, in regard to PQOs. Examples include PQLs and QC sample limits (precision/accuracy).	ESAT Data Validation			
IIb	Field duplicates	Compare results of field duplicate (or replicate) analyses with RPD criteria	ESAT Data Validation			

## QAPP Worksheet #36: Validation (Steps IIa and IIb) Summary Table

Step IIa/IIb	Matrix	Analytical Group	Concentration Level	Validation Criteria	Data Validator (title and organizational affiliation)
IIa / IIb	Soil	Total lead – C-109	Low	Refer to DESA Laboratory Method C-109 (TAL ICP-AES)	EPA DESA Data Validation Personnel
IIa / IIb	Air	Total lead – ISMO1.3	Low	Data validation SOP for Inorganic Analysis of L/M Concentration Metals under- SOW ISMO1.2 SOP HW-2, Rev 1.3	ESAT Data Validation Personnel

### QAPP Worksheet #37: Usability Assessment

Summarize the usability assessment process and all procedures, including interim steps and any statistics, equations, and computer algorithms that will be used: Data, whether generated in the field or by the laboratory, are tabulated and reviewed for Precision, Accuracy, Representativeness, Completeness, and Comparability (PARCCS) by the SPM for field data or the data validator for laboratory data. The review of the PARCC Data Quality Indicators (DQI) will compare with the DQO detailed in the site-specific QAPP, the analytical methods used and impact of any qualitative and quantitative trends will be examined to determine if bias exists. A hard copy of field data is maintained in a designated field or site logbook. Laboratory data packages are validated, and final data reports are generated. All documents and logbooks are assigned unique and specific control numbers to allow tracking and management.

Questions about Non-CLP data, as observed during the data review process, are resolved by contacting the respective site personnel and laboratories as appropriate for resolution. All communications are documented in the data validation record with comments as to the resolution to the observed deficiencies.

Where applicable, the following documents will be followed to evaluate data for fitness in decision making: EPA QA/G-4, <u>Guidance on Systematic Planning using the Data Quality Objectives Process</u>, EPA/240/B-06/001, February 2006, and EPA QA/G-9R, <u>Guidance for Data Quality Assessment</u>, A reviewer's Guide EPA/240/B-06/002, February 2006.

### Describe the evaluative procedures used to assess overall measurement error associated with the project:

As delineated in the Uniform Federal Policy for Implementing Environmental Quality Systems: Evaluating, Assessing and Documenting Environmental Data Collection and Use Programs Part 1: UFP-QAPP (EPA-505-B-04-900A, March 2005); Part 2A: UFP-QAPP Workbook (EPA-505-B-04-900C, March 2005); Part 2B: Quality Assurance/Quality Control Compendium: Non-Time Critical QA/QC Activities (EPA-505-B-04-900B, March 2005); "Graded Approach" will be implemented for data collection activities that are either exploratory in nature or where specific decisions cannot be identified, since this guidance indicates that the formal DQO process is not necessary.

### QAPP Worksheet #37: Usability Assessment (Concluded)

The EPA is conducting the Removal Action as described above to mitigate exposure of airborne lead-contaminated soil and exposure to lead-contaminated soil along the perimeter of the Site. Perimeter air samples collected daily will be analyzed for total lead. Post-excavation soil samples will be collected to be analyzed for total lead. Results will be compared to NYDEC and EPA soil clean-up criteria to determine if concentrations of lead may represent a threat to human health.


Identify the personnel responsible for performing the usability assessment: Site Project Management Team, and EPA, Region II OSC

Describe the documentation that will be generated during usability assessment and how usability assessment results will be presented so that they identify trends, relationships (correlations), and anomalies:

A copy of the most current approved QAPP, including any graphs, maps and text reports developed will be provided to all personnel identified on the distribution list.

Attachment A

Site Location Map



Attachment B

Sampling SOPs



### **GENERAL FIELD** SAMPLING GUIDELINES

SOP#: 2001 DATE: 08/11/94

REV. #: 0.0

#### 1.0 SCOPE AND APPLICATION

The purpose of this Standard Operating Procedure (SOP) is to provide general field sampling guidelines that will assist REAC personnel in choosing sampling strategies, location, and frequency for proper assessment of site characteristics. This SOP is applicable to all field activities that involve sampling.

These are standard (i.e., typically applicable) operating procedures which may be varied or changed as required, dependent on site conditions, equipment limitations or limitations imposed by the procedure. In all instances, the ultimate procedures employed should be documented and associated with the final report.

Mention of trade names or commercial products does constitute U.S. EPA endorsement or recommendation for use.

#### 2.0 METHOD SUMMARY

Sampling is the selection of a representative portion of a larger population, universe, or body. Through examination of a sample, the characteristics of the larger body from which the sample was drawn can be inferred. In this manner, sampling can be a valuable tool for determining the presence, type, and extent of contamination by hazardous substances in the environment.

The primary objective of all sampling activities is to characterize a hazardous waste site accurately so that its impact on human health and the environment can be properly evaluated. It is only through sampling and analysis that site hazards can be measured and the job of cleanup and restoration can be accomplished effectively with minimal risk. The sampling itself must be conducted so that every sample collected retains its original physical form and chemical composition. In this way, sample integrity is insured, quality assurance standards are maintained, and the sample can accurately represent the larger body of

material under investigation.

The extent to which valid inferences can be drawn from a sample depends on the degree to which the sampling effort conforms to the project's objectives. For example, as few as one sample may produce adequate, technically valid data to address the project's objectives. Meeting the project's objectives requires thorough planning of sampling activities, and implementation of the most appropriate sampling and analytical procedures. These issues will be discussed in this procedure.

#### 3.0 **SAMPLE** PRESERVATION, CONTAINERS, HANDLING, AND STORAGE

The amount of sample to be collected, and the proper sample container type (i.e., glass, plastic), chemical preservation, and storage requirements are dependent on the matrix being sampled and the parameter(s) of interest. Sample preservation, containers, handling, and storage for air and waste samples are discussed in the specific SOPs for air and waste sampling techniques.

#### INTERFERENCES 4.0 AND POTENTIAL PROBLEMS

The nature of the object or materials being sampled may be a potential problem to the sampler. If a material is homogeneous, it will generally have a uniform composition throughout. In this case, any sample increment can be considered representative of the material. On the other hand, heterogeneous samples present problems to the sampler because of changes in the material over distance, both laterally and vertically.

Samples of hazardous materials may pose a safety threat to both field and laboratory personnel. Proper health and safety precautions should be implemented when handling this type of sample.

Environmental conditions, weather conditions, or non-target chemicals may cause problems and/or interferences when performing sampling activities or when sampling for a specific parameter. Refer to the specific SOPs for sampling techniques.

### 5.0 EQUIPMENT/APPARATUS

The equipment/apparatus required to collect samples must be determined on a site specific basis. Due to the wide variety of sampling equipment available, refer to the specific SOPs for sampling techniques which include lists of the equipment/apparatus required for sampling.

### 6.0 REAGENTS

Reagents may be utilized for preservation of samples and for decontamination of sampling equipment. The preservatives required are specified by the analysis to be performed. Decontamination solutions are specified in ERT SOP #2006, Sampling Equipment Decontamination.

### 7.0 PROCEDURE

### 7.1 Types of Samples

In relation to the media to be sampled, two basic types of samples can be considered: the environmental sample and the hazardous sample.

Environmental samples are those collected from streams, ponds, lakes, wells, and are off-site samples that are not expected to be contaminated with hazardous materials. They usually do not require the special handling procedures typically used for concentrated wastes. However, in certain instances, environmental samples can contain elevated concentrations of pollutants and in such cases would have to be handled as hazardous samples.

Hazardous or concentrated samples are those collected from drums, tanks, lagoons, pits, waste piles, fresh spills, or areas previously identified as contaminated, and require special handling procedures because of their potential toxicity or hazard. These samples can be further subdivided based on their degree of hazard; however, care should be taken when handling and shipping any wastes believed to be concentrated regardless of the degree.

The importance of making the distinction between environmental and hazardous samples is two-fold:

- (1) Personnel safety requirements: Any sample thought to contain enough hazardous materials to pose a safety threat should be designated as hazardous and handled in a manner which ensures the safety of both field and laboratory personnel.
- (2) Transportation requirements: Hazardous samples must be packaged, labeled, and shipped according to the International Air Transport Association (IATA) Dangerous Goods Regulations or Department of Transportation (DOT) regulations and U.S. EPA guidelines.

### 7.2 Sample Collection Techniques

In general, two basic types of sample collection techniques are recognized, both of which can be used for either environmental or hazardous samples.

### **Grab Samples**

A grab sample is defined as a discrete aliquot representative of a specific location at a given point in time. The sample is collected all at once at one particular point in the sample medium. The representativeness of such samples is defined by the nature of the materials being sampled. In general, as sources vary over time and distance, the representativeness of grab samples will decrease.

#### Composite Samples

Composites are nondiscrete samples composed of more than one specific aliquot collected at various sampling locations and/or different points in time. Analysis of this type of sample produces an average value and can in certain instances be used as an alternative to analyzing a number of individual grab samples and calculating an average value. It should be noted, however, that compositing can mask problems by diluting isolated concentrations of some hazardous compounds below detection limits.

Compositing is often used for environmental samples and may be used for hazardous samples under certain conditions. For example, compositing of hazardous waste is often performed after compatibility tests have been completed to determine an average value over a number of different locations (group of drums). This procedure generates data that can be useful by providing an average concentration within a number of units, can serve to keep analytical costs down, and can provide information useful to transporters and waste disposal operations.

For sampling situations involving hazardous wastes, grab sampling techniques are generally preferred because grab sampling minimizes the amount of time sampling personnel must be in contact with the wastes, reduces risks associated with compositing unknowns, and eliminates chemical changes that might occur due to compositing.

### 7.3 Types of Sampling Strategies

The number of samples that should be collected and analyzed depends on the objective of the investigation. There are three basic sampling strategies: random, systematic, and judgmental sampling.

Random sampling involves collection of samples in a nonsystematic fashion from the entire site or a specific portion of a site. Systematic sampling involves collection of samples based on a grid or a pattern which has been previously established. When judgmental sampling is performed, samples are collected only from the portion(s) of the site most likely to be contaminated. Often, a combination of these strategies is the best approach depending on the type of the suspected/known contamination, the uniformity and size of the site, the level/type of information desired, etc.

### 7.4 QA Work Plans (QAWP)

A QAWP is required when it becomes evident that a field investigation is necessary. It should be initiated in conjunction with, or immediately following, notification of the field investigation. This plan should be clear and concise and should detail the following basic components, with regard to sampling activities:

- C Objective and purpose of the investigation.
- C Basis upon which data will be evaluated.
- Information known about the site including location, type and size of the facility, and length of operations/abandonment.
- C Type and volume of contaminated material, contaminants of concern (including

- concentration), and basis of the information/data.
- C Technical approach including media/matrix to be sampled, sampling equipment to be used, sample equipment decontamination (if necessary), sampling design and rationale, and SOPs or description of the procedure to be implemented.
- Project management and reporting, schedule, project organization and responsibilities, manpower and cost projections, and required deliverables.
- QA objectives and protocols including tables summarizing field sampling and QA/QC analysis and objectives.

Note that this list of QAWP components is not allinclusive and that additional elements may be added or altered depending on the specific requirements of the field investigation. It should also be recognized that although a detailed QAWP is quite important, it may be impractical in some instances. Emergency responses and accidental spills are prime examples of such instances where time might prohibit the development of site-specific QAWPs prior to field activities. In such cases, investigators would have to rely on general guidelines and personal judgment, and the sampling or response plans might simply be a strategy based on preliminary information and finalized on site. In any event, a plan of action should be developed, no matter how concise or informal, to aid investigators in maintaining a logical and consistent order to the implementation of their task.

### 7.5 Legal Implications

The data derived from sampling activities are often introduced as critical evidence during litigation of a hazardous waste site cleanup. Legal issues in which sampling data are important may include cleanup cost recovery, identification of pollution sources and responsible parties, and technical validation of remedial design methodologies. Because of the potential for involvement in legal actions, strict adherence to technical and administrative SOPs is essential during both the development and implementation of sampling activities.

Technically valid sampling begins with thorough planning and continues through the sample collection and analytical procedures. Administrative requirements involve thorough, accurate

documentation of all sampling activities. Documentation requirements include maintenance of a chain of custody, as well as accurate records of field activities and analytical instructions. Failure to observe these procedures fully and consistently may result in data that are questionable, invalid and non-defensible in court, and the consequent loss of enforcement proceedings.

### 8.0 CALCULATIONS

Refer to the specific SOPs for any calculations which are associated with sampling techniques.

### 9.0 QUALITY ASSURANCE/ QUALITY CONTROL

Refer to the specific SOPs for the type and frequency of QA/QC samples to be analyzed, the acceptance criteria for the QA/QC samples, and any other QA/QC activities which are associated with sampling techniques.

### 10.0 DATA VALIDATION

Refer to the specific SOPs for data validation activities that are associated with sampling techniques.

### 11.0 HEALTH AND SAFETY

When working with potentially hazardous materials, follow U.S. EPA, OSHA, and corporate health and safety procedures.



# GENERAL AIR SAMPLING GUIDELINES

SOP#: 2008 DATE: 11/16/94 REV. #: 0.0

### 1.0 SCOPE AND APPLICATION

This Standard Operating Procedure (SOP) provides guidance in developing and implementing sampling plans to assess the impact of hazardous waste sites on ambient air. It presents the United States Environmental Protection Agency/Environmental Response Team's (U.S. EPA/ERT's) approach to air sampling and monitoring and identifies equipment requirements. It is not within the scope of this SOP to provide a generic air sampling plan. Experience, objectives, site characteristics, and chemical characteristics will dictate sampling strategy. This SOP does not address indoor air sampling.

Two basic approaches can be used to assess ambient air (also referred to as air pathway assessments): modeling and measurements. The modeling approach initially estimates or measures the overall site emission rate(s) and pattern(s). These data are input into an appropriate air dispersion model, which predicts either the maximum or average air concentrations at selected locations or distances during the time period of concern. This overall modeling strategy is presented in the first three volumes of the Air Superfund National Technical Guidance Series on Air Pathway Assessments<sup>(1,2,3)</sup>. Specific applications of this strategy are presented in several additional Air Superfund Technical Guidance documents<sup>(4)</sup>.

The measurement approach involves actually measuring the air impact at selected locations during specific time periods. These measurements can be used to document actual air impacts during specific time intervals (i.e., during cleanup operations) or to extrapolate the probable "worst case" concentrations at that and similar locations over a longer time period than was sampled.

This SOP addresses issues associated with this second assessment strategy. This SOP also discusses the U.S. EPA/ERT's monitoring instruments, air sampling

kits, and approach to air sampling and monitoring at hazardous waste sites.

These are standard (i.e., typically applicable) operating procedures which may be varied or changed as required, depending on site conditions, equipment limitations, or limitations imposed by the procedure. In all instances, the ultimate procedures employed should be documented and associated with the final report.

Mention of trade names or commercial products does not constitute U.S. EPA endorsement or recommendation for use.

### 2.0 METHOD SUMMARY

Air monitoring is defined as the use of direct-reading instruments and other screening or monitoring equipment and techniques that provide instantaneous (real-time) data on the levels of airborne contaminants. The U.S. EPA/ERT maintains numerous monitors for real-time measurements. Examples of air monitoring equipment are hand-held photoionization detectors (PID), flame ionization detectors (FID), oxygen/combustible gas detectors, and remote optical sensors.

Air sampling is defined as those sampling and analytical techniques that require either off- or on-site laboratory analysis and therefore do not provide immediate results. Typically, air sampling occurs after use of real-time air monitoring equipment has narrowed the number of possible contaminants and has provided some qualitative measurement of contaminant concentration. Air sampling techniques are used to more accurately detect, identify and quantify specific chemical compounds relative to the majority of air monitoring technologies.

In the Superfund Removal Program, On-Scene Coordinators (OSCs) may request the U.S. EPA/ERT to conduct air monitoring and sampling during the

following situations: emergency responses, site assessments, and removal activities. Each of these activities has a related air monitoring/sampling objective that is used to determine the potential hazards to workers and/or the community.

### **C** Emergency Response

Emergency responses are immediate responses to a release or threatened release of hazardous substances presenting an imminent danger to public health, welfare, or the environment (i.e., chemical spills, fires, or chemical process failures resulting in a controlled release of hazardous substances). Generally these situations require rapid onsite investigation and response. A major part of this investigation consists of assessing the air impact of these releases.

### C Removal Site Assessment

Removal site assessments (referred to as site assessments) are defined as any of several activities undertaken to determine the extent of contamination at a site and which help to formulate the appropriate response to a release or threatened release of hazardous substances. These activities may include a site inspection, multimedia sampling, and other data collection.

#### C Removal Actions

Removal actions clean up or remove hazardous substances released into the environment. Removal actions include any activity conducted to abate, prevent, minimize, stabilize, or eliminate a threat to public health or welfare, or to the environment.

Personal risk from airborne contaminants can be determined by comparing the results of on-site monitoring and sampling to health-based action levels such as the American Conference of Governmental Industrial Hygienists (ACGIH) Threshold Limit Values (TLVs) and the Occupational Safety and Health Administration (OSHA) Permissible Exposure Limits (PELs). Residential risk can be determined by comparing the results of off-site monitoring or sampling to health-based action levels such as those developed by the Agency for Toxic Substance and

Disease Registry (ATSDR).

The extent to which valid inferences can be drawn from air monitoring/sampling depends on the degree to which the monitoring/sampling effort conforms to the objectives of the event. Meeting the project's objectives requires thorough planning of the monitoring/sampling activities, and implementation of the most appropriate monitoring/sampling and analytical procedures. These issues will be discussed in this SOP.

### 3.0 SAMPLE PRESERVATION, CONTAINERS, HANDLING, AND STORAGE

Preservation, containers, handling and storage for air samples are discussed in the specific SOPs for the technique selected. In addition, the analytical method (i.e., U.S. EPA, National Institute for Occupational Safety and Health [NIOSH], and OSHA Methods) may be consulted for storage temperature, holding times and packaging requirements. After sample collection, the sampling media (i.e., cassettes or tubes) are immediately sealed. The samples are then placed into suitable containers (i.e., whirl bags, resealable bagsor culture tubes) which are then placed into a shipping container.

Use bubble wrap or styrofoam peanuts when packing air samples for shipment. DO NOT USE VERMICULITE.

## 4.0 INTERFERENCES AND POTENTIAL PROBLEMS

Upwind sources can contribute to sample concentration. Natural sources, such as biological waste, can produce hydrogen sulfide and methane which may contribute to the overall contaminant level. Extraneous anthropogenic contaminants (i.e., burning of fossil fuels; emissions from vehicular traffic, especially diesel; volatile compounds from petrochemical facilities; and effluvium from smoke stacks) may also contribute. Air sampling stations should be strategically placed to identify contributing sources.

Photoreactivity or reaction of the parameters of concern may occur with nonrelated compounds [i.e., nitrogen compounds and polyaromatic hydrocarbons

(PAHs)]. Some sorbent media/samples should not be exposed to light during or after sampling due to photochemical effects (i.e., PAHs).

Various environmental factors, including humidity, temperature and pressure, also impact the air sampling methodology, collection efficiency and detection limit. Since the determination of air contaminants is specifically dependent on the collection parameters and efficiencies, the collection procedure is an integral part of the analytical method.

Detection limits depend on the contaminants being investigated and the particular site situation. It is important to know why the data are needed and how the data will be used. Care should be taken to ensure the detection limits are adequate for the intended use of the final results.

Some equipment may be sensitive to humidity and temperature extremes.

### 5.0 EQUIPMENT/APPARATUS

## 5.1 Direct Reading Instruments (Air Monitoring Instruments)

There are two general types of direct reading. instruments: portable screening devices and specialized analytical instruments. Generally all these techniques involve acquiring, for a specific location or area, continuous or sequential direct air concentrations in either a real-time or semi-real-time mode. None of these instruments acquires true time-weighted average concentrations. In addition, these instruments are not capable of acquiring simultaneous concentration readings at multiple locations, although several are able to sequentially analyze samples taken remotely from different locations. The document, "Guide to Portable Instruments for Assessing Airborne Pollutants Arising from Hazardous Waste Sites<sup>(5)</sup>," provides additional information about air sampling and monitoring. The hazard levels for airborne contaminants vary. See the ACGIH TLVs and the OSHA PELs for safe working levels. Common screening devices and analytical instruments are described in Appendix A.

## 5.2 Air Sampling Equipment and Media/Devices

The U.S. EPA/ERT uses the following analytical

methods for sampling: NIOSH Manual of Analytical Methods<sup>(6)</sup>, American Society for Testing and Materials (ASTM) Methods<sup>(7)</sup>, U.S. EPA Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air<sup>(8,9)</sup>, and OSHA Methods<sup>(10)</sup>. Additional air sampling references include Industrial Hygiene and Toxicology (3rd Ed)<sup>(11)</sup> and Air Sampling Instruments for Evaluation of Atmospheric Contaminants<sup>(12)</sup>. These methods typically specify equipment requirements for sampling. Since air sampling is such a diverse technology, no single method or reference is best for all applications. Common sampling equipment and media/devices are described in Appendix B.

## 5.3 Tools/Material and Equipment List

In addition to equipment and materials identified in Appendices A and B, the following equipment and materials may be required to conduct air sampling and monitoring at hazardous waste sites:

- Camera
- C Site logbook
- C Clipboard
- Chain of custody records
- Custody seals
- C Air sampling worksheets
- C Sample labels
- C Small screwdriver set
- C Aluminum foil
- C Extension cords
- C Glass cracker
- C Multiple plug outlet
- C Whirl bags or culture tubes
- C Teflon tape
- Calibration devices
- C Tygon and/or Teflon<sup>R</sup> tubing
- C Surgical gloves
- C Lint-free gloves
- C Ice
- C Sample container

Use the following additional equipment when decontaminating glassware on site:

- Protective equipment (i.e., gloves, splash goggles, etc.)
- C Appropriate solvent(s)
- C Spray bottles
- C Liquinox (soap)
- C Paper towels

- C Distilled/deionized water
- C Five-gallon buckets
- C Scrub brushes and bottle brushes

### 6.0 REAGENTS

Impinger sampling involves using reagents contained in a glass vial to absorb contaminants of concern (for example, NIOSH Method 3500 for formaldehyde uses 1% sodium bisulfite solution). Impinger solutions vary and are method-dependent.

Reagents such as acetone and hexane are required to decontaminate glassware and some air sampling equipment. Decontamination solutions are specified in the Sampling Equipment Decontamination SOP.

### 7.0 PROCEDURES

### 7.1 Air Monitoring Design

### 7.1.1 Initial Surveys

In general, the initial survey is considered to be a relatively rapid screening process for collecting preliminary data at hazardous waste sites. However, initial surveys may require many hours to complete and may consist of more than one entry.

Some information is generally known about the site; therefore, real-time instrumentation for specific compounds (i.e., detector tubes and electrochemical sensors) can be used to identify hot spots. Sufficient data should be obtained with real-time instruments during the initial entry to screen the site for various contaminants. When warranted, intrinsically safe or explosion-proof instruments should be used. An organic vapor analyzer (OVA) is typically used during this survey. These gross measurements may be used on a preliminary basis to (1) determine levels of personal protection, (2) establish site work zones, and (3) map candidate areas for more thorough qualitative and quantitative studies involving air sampling.

In some situations, the information obtained may be sufficient to preclude additional monitoring. Materials detected during the initial survey may call for a more comprehensive evaluation of hazards and analyses for specific compounds. Since site activities and weather conditions change, a continuous program to monitor the ambient atmosphere must be established.

### 7.1.2 Off-Site Monitoring

Typically, perimeter monitoring with the same instruments employed for on-site monitoring is utilized to determine site boundaries. Because air is a dynamic matrix, physical boundaries like property lines and fences do not necessarily delineate the site boundary or area influenced by a release. Whenever possible, atmospheric hazards in the areas adjacent to the on-site zone should be monitored with directreading instruments. Monitoring at the fenceline or at varying locations off site provides useful information regarding pollutant migration. Three to four locations downwind of the source (i.e., plume) at breathingzone height, provide a basic fingerprint of the plume. Negative instrument readings off site should not be interpreted as the complete absence of airborne toxic substances; rather, they should be considered another piece of information to assist in the preliminary evaluation. The interpretation of negative readings is instrument-dependent. The lack of instrument readings off site should not be interpreted as the complete absence of all airborne toxic substances; rather, it is possible that the particular compound or class of compounds to which the monitoring instrument responds is not present or that the concentration of the compound(s) is below the instrument's detection limit.

### 7.2 Air Sampling Design

### 7.2.1 Sampling Plan Design

The goal of air sampling is to accurately assess the impact of a contaminant source(s) on ambient air quality. This impact is expressed in terms of overall average and/or maximum air concentrations for the time period of concern and may be affected by the transport and release of pollutants from both on- and off-site sources. The location of these sources must be taken into account as they impact the selection of sampling locations. Unlike soil and groundwater concentrations, air concentrations at points of interest can easily vary by orders of magnitude over the period of concern. This variability plays a major role in designing an air sampling plan.

Downwind air concentration is determined by the amount of material being released from the site into the air (the emission rate) and by the degree that the contamination is diluted as it is transported. Local

meteorology and topography govern downwind dilution. Contaminant emission rates can also be heavily influenced by on-site meteorology and on-site activities. All of these concerns must be incorporated into an air sampling plan.

A sampling strategy can be simple or complex, depending on the sampling program objectives. Programs involving characterization of the pollutant contribution from a single point source tend to be simple, whereas sampling programs investigating fate and transport characteristics of components from diverse sources require a more complex sampling strategy. In addition, resource constraints may affect the complexity of the sampling design.

An optimal sampling strategy accounts for the following site parameters:

- C Location of stationary as well as mobile sources
- C Analytes of concern
- C Analytical detection limit to be achieved
- Rate of release and transport of pollutants from sources
- C Availability of space and utilities for operating sampling equipment
- C Meteorological monitoring data
- Meteorological conditions in which sampling is to be conducted

The sampling strategy typically requires that the concentration of contaminants at the source or area of concern as well as background contributions be quantified. It is important to establish background levels of contaminants in order to develop a reference point from which to evaluate the source data. Field blanks and lot blanks, as well as various other types of QA/QC samples, can be utilized to determine other sources. The impact of extraneous sources on sampling results can frequently be accounted for by placing samplers upwind, downwind and crosswind from the subject source. The analytical data from these different sampling locations may be compared to determine statistical differences.

### 7.2.2 Sampling Objectives

The objectives of the sampling must be determined prior to developing the sampling plan. Does the sampling plan verify adequate levels of protection for on-site personnel, or address potential off-site impacts associated with the site or with site activities? In addition, the assumptions associated with the sampling program must be defined. These assumptions include whether the sampling is to take place under "typical," "worst case," or "one-time" conditions. If the conditions present at the time of sampling are different from those assumed during the development of the sampling plan, then quality of the data collected may be affected. The following definitions have been established:

- C Typical: routine daily sampling or routine scheduled sampling at pre-established locations.
- Worst case: sampling conducted under the worst meteorological and/or site conditions which would result in elevated ambient concentrations.
- One-time: only one chance is given to collect a sample without regard to time or conditions.

Qualitative data acquired under these conditions are usually applicable only to the time period during which the data were collected and may not provide accurate information to be used in estimating the magnitude of an air impact during other periods or over a long time interval.

The sampling objectives also dictate the detection limits. Sampling methods for airborne contaminants will depend upon the nature and state (solid, liquid or gas) of the contaminant. Gases and vapors may be collected in aqueous media or adsorbents, in molecular sieves, or in suitable containers. Particulates are collected by filters or impactors. The volume of sample to be collected is dependent upon an estimate of the contaminant concentration in the air, the sensitivity of the analytical method, and the standard or desired detection limit. A sufficient amount of sample must be collected to achieve the desired detection limit without interference from other contaminants. In addition, the selected method must be able to detect the target compound(s).

## 7.2.3 Location and Number of Individual Sampling Points

Choose the number and location of sampling points according to the variability, or sensitivity, of the sampling and analytical methods being utilized, the variability of contaminant concentration over time at the site, the level of precision required and costlimitations. In addition, determine the number of locations and placement of samplers by considering the nature of the response, local terrain, meteorological conditions, location of the site (with respect to other conflicting background sources), size of the site, and the number, size, and relative proximity of separate on-site emission sources and upwind sources. The following are several considerations for sampler placement:

- C Location of potential on-site emission sources, as identified from the review of site background information or from preliminary on-site inspections.
- C Location of potential off-site emission sources upwind of the sampling location(s). Review local wind patterns to determine the location of off-site sources relative to wind direction.

C Topographic features that affect the dispersion and transport of airborne toxic constituents.

Avoid natural obstructions when choosing air sampling station locations, and account for channelization around those obstructions.

- C Large water bodies, which affect atmospheric stability and the dispersion of air contaminants.
- Roadways (dirt or paved), which may generate dust that could mask site contaminants.
- Vegetation, such as trees and shrubs, which stabilizes soil and retards subsurface contaminants from becoming airborne. It also affects air flow and scrubs some contaminants from the air. Sometimes thick vegetation can make an otherwise ideal air monitoring location inaccessible.

Consider the duration of sampling activities when choosing the location and number of samples to be collected. For example, if the sampling period is limited to a few hours, one or two upwind and several downwind samples would typically be adequate, especially around major emission sources.

A short-term monitoring program ranges from several days to a few weeks and generally includes gathering data for site assessments, removal actions, and source determination data (for further modeling). Activities involved in a short-term sampling strategy must make the most of the limited possibilities for data collection. Consider moving upwind/downwind locations daily based on National Oceanic and Atmospheric Administration (NOAA) weather forecasts. Weather monitoring becomes critical where complex terrain and local meteorological effects frequently change wind direction. Often, a number of alternatives can fulfill the same objective.

Prevailing winds running the length of a valley usually require a minimum number of sampler locations; however, a complex valley may require more sampler locations to account for the wide variety of winds. Ocean/lake effects may require a radical plan to collect enough samples to reach a low detection limit. Two sets of samplers may be placed next to each other: one set would be activated during the sea breeze

while the other set is turned off, and vice versa when there is no sea breeze. After the sampling event, the respective upwind and downwind samples would be combined. Another alternative for sampling near a large body of water may be to use automatic, wind-vector-operated samplers, which turn the sampler on only when the wind comes from a specified vector. At sites located on hillsides, wind will move down a valley and produce an upward fetch at the same time. Sampling locations may have to ring the site to measure the wind's impact.

Off-site sources may affect on-site monitoring. In this case, on-site meteorological data, concurrent with sampling data, is essential to interpreting the acquired data. Also, additional upwind sampling sites may be needed to fully characterize ambient background contaminant levels. Multiple off-site sources may require several monitoring locations, but if the sources are at a sufficient distance, only one monitoring location is needed.

Topography and weather are not the only factors in sampler location; the sampling sites must be secure from vandals and mishap. Secure all sampling locations to maintain chain of custody, and to prevent tampering with samples or loss of sampling units. High-volume sampling methods often require the use of 110 VAC electric power. When portable generators are used, the power quality may affect sampler operation. Also, be aware that the generators themselves could be a potential pollution source if their placement is not carefully considered.

Air quality dispersion models can be used to place samplers. The models incorporate source information, surrounding topography, and meteorological data to predict the general distance and directions of maximum ambient concentrations. Modeling results should be used to select sampling locations in areas of maximum pollutant concentrations.

## 7.2.4 Time, Duration and Frequency of Sampling Events

After choosing appropriate sampling or monitoring locations, determine the sampling frequency and the number of samples to be collected. The time of day, duration and frequency of sampling events is governed by:

The effects of site activities and meteorology

- on emission rates
- C The diurnal effect of the meteorology on downwind dispersion
- C The time period(s) of concern as defined by the objective
- C The variability in the impact from other nonsite-related sources
- If defined, the degree of confidence needed for either the mean or maximum downwind concentrations observed
- C The precision requirements for single measurements
- Cost and other logistical considerations

The duration of the removal action and the number of hours per day that site work is conducted determine the time, duration, and frequency of samples. Shortterm sampling programs may require daily sampling, while long-term programs may require 24-hour sampling every sixth or twelfth day. If the site will be undergoing removal activities 24 hours a day, continuous air sampling may be warranted. However, if the site activities will be conducted for only eight hours a day, and there are no emissions likely to occur during the remaining 16 hours, then sampling would be appropriate prior to the start of daily activities, would continue during operations, and end at the conclusion of the daily activities. An off-peak sample collection can ensure that emissions are not persisting after the conclusion of daily cleanup activities. For some sites, emissions are still a factor several hours after daily site activities have been completed. Because of the typically decreased downwind dispersion in the evening, higher downwind concentrations than were present during daytime site activities may be detected. For sites where this is possible, the sampling duration needs to be lengthened accordingly.

Sampling duration and flow rate dictate the volume of air collected, and to a major degree, the detection limit. The analytical method selected will provide a reference to flow rate and volume. Flow rates are limited to the capacity of the pumps being employed and the contact time required by the collection media.

The duration or period of air sampling is commonly divided into two categories (1) samples collected over a brief time period are referred to as "instantaneous" or "grab" samples and are usually collected in less than five minutes and (2) average or integrated samples are collected over a significantly longer period of time. Integrated samples provide an average

concentration over the entire sampling period. Integrated samples are not suited to determining cyclical releases of contaminants because periodic or cyclical events are averaged out by the proportionally long sampling duration.

Air quality dispersion models can predict the maximum air contaminant concentration expected from a source. The meteorological and site conditions expected to cause the highest concentration are known as worst-case conditions and can be identified by analyzing the modeling results. Depending upon the objective, one may sample when the model predicts worst-case conditions will exist.

## 7.2.5 Meteorological and Physical/Chemical Considerations

A meteorological monitoring program is an integral part of site monitoring activities. Meteorological data, which define local terrain impacts on air flow paths, are needed to interpret air concentration data. Meteorological data may be available from an existing station located near the site (i.e., at a local airport), otherwise a station should be set up at the site. This data will document the degree that samples actually were downwind and verify whether other worst-case assumptions were met. Meteorological parameters to be monitored are, at a minimum, wind speed, wind direction, and sigma theta (which is the horizontal wind direction standard deviation and an indicator of atmospheric stability). The remaining parameters primarily affect the amount of a contaminant available in the air.

### C Wind Speed

When the contaminant of concern is a particulate, wind speed is critical in determining whether the particulate will become airborne, the quantity of the particulate that becomes airborne, and the distance the particulate will travel from the source. Wind speed also contributes to the volatilization of contaminants from liquid sources.

#### C Wind Direction

Wind direction highly influences the path of airborne contaminants. In addition, variations in wind direction increase the dispersion of pollutants from a given source.

### C Atmospheric Stability

Atmospheric stability refers to the degree to which the atmosphere tends to dampen vertical and horizontal motion. Stable atmospheric conditions (i.e., evenings) result in low dispersion, and unstable atmospheric conditions (i.e., hot sunny days) result in higher dispersion.

#### C Temperature

Higher temperatures increase the rate of volatilization of organic and some inorganic compounds and affect the initial rise of gaseous or vapor contaminants. Therefore, worst-case emission of volatiles and semivolatiles occurs at the hottest time of day, or on the hottest day.

### C Humidity

High humidity affects water-soluble chemicals and particulates. Humid conditions may dictate the sampling media used to collect the air sample, or limit the volume of air sampled and thereby increase the detection limit.

### C Atmospheric Pressure

Migration of landfill gases through the landfill surface and through surrounding soils are governed by changes in atmospheric pressure. Atmospheric pressure will influence upward migration of gaseous contaminants from shallow aquifers into the basements of overlying structures.

In many cases, the transport and dispersion of air pollutants is complicated by local meteorology. Normal diurnal variations (i.e., temperature inversions) affect dispersion of airborne contaminants. Terrain features can enhance or create air inversions and can also influence the path and speed of air flow, complicating transport and dispersion patterns.

The chemical characteristics of a contaminant (i.e., molecular weight, physical

state, vapor pressure, aerodynamic size, temperature, reactive compounds, and photodegradation) affects its behavior and can influence the method used to sample and analyze it.

#### 8.0 CALCULATIONS

Volume is obtained by multiplying the sample time in minutes by the flow rate. Sample volume should be indicated on the chain of custody record. Adjustments for temperature and pressure differences may be required.

Results are usually provided in parts per million (ppm), parts per billion (ppb), milligrams per cubic meter (mg/m³) or micrograms per cubic meter (µg/m³).

Refer to the analytical method or regulatory guidelines for other applicable calculations.

### 9.0 QUALITYASSURANCE/ QUALITY CONTROL

The manufacturer's instructions should be reviewed prior to instrument use. Instruments must be utilized in accordance with manufacturer's instructions. Equipment checkout and calibration activities must occur prior to and after monitoring and sampling and must be documented.

### 9.1 QA/QC Samples

QA/QC samples provide information on the variability and usability of environmental sample results. Various QA/QC samples may be collected to detect error. QA/QC samples are submitted with the field samples for analysis to aid in identifying the origin of analytical discrepancies; then a determination can be made as to how the analytical results should be used: Collocated samples, background samples, field blanks, and lot blanks are the most commonly collected QA/QC field samples. Performance evaluation (PE) samples and matrix spikes provide additional measures of data QA/QC control. QA/QC results may suggest the need for modifying sample collection, preparation, handling, or analytical procedures if the resultant data do not meet sitespecific QA or data quality objectives.

### 9.2 Sample Documentation

All sample and monitoring activities should be documented legibly, in ink. Any corrections or revisions should be made by lining through the incorrect entry and by initialing the error. All samples must be recorded on an Air Sampling Worksheet. A chain of custody record must be maintained from the time a sample is taken to the final deposition of the sample. Custody seals demonstrate that a sample container has not been opened or tampered with during transport or storage of samples.

### 10.0 DATA VALIDATION

Results for QA/QC samples should be evaluated for contamination. This information should be utilized to qualify the environmental sample results accordingly with data quality objectives.

### 11.0 HEALTH AND SAFETY

Personal protection equipment (PPE) requirements identified in federal and/or state regulations and 29 Code of Federal Regulations (CFR) 1910.120 for hazardous waste site work must be followed.

The majority of physical precautions involved in air sampling are related to the contaminant sampled. Attention should be given when sampling in potentially explosive, flammable or acidic atmospheres. On rare occasions, the collection media may be hazardous; for example, in the instance where an acidic or basic solution is utilized in an impinger.

When working with potentially hazardous materials, follow U.S. EPA, OSHA and corporate health and safety procedures.

### 12.0 REFERENCES

- U.S. EPA. Air Superfund National Technical Guidance Series. Volume I. Application of Air Pathway Analyses for Superfund Activities. EPA/450/1-89/001.
- U.S. EPA. Air Superfund National Technical Guidance Series. Volume II. Estimation of Baseline Air Emissions at Superfund Sites. EPA/450/1-89/002.
- U.S. EPA. Air Superfund National Technical Guidance Series. Volume III.

- Estimations of Air Emissions from Cleanup Activities at Superfund Sites. EPA/450/1-89/003.
- (4) U.S. EPA. Air Superfund National Technical Guidance Series. Volume IV. Procedures for Dispersion Air Modeling and Air Monitoring for Superfund Air Pathway Analysis. EPA/450/1-89/004.
- (5) Guide to Portable Instruments for Assessing Airborne Pollutants Arising Wastes. Hazardous International Organization of Legal Metrology (OIML) U.S. National Working Group (NWG) for American OIML, -Conference Governmental Industrial Hygienists, Cincinnati, OH

- (6) NIOSH. Manual of Analytical Methods, Second Edition. Volumes 1-7. U.S. Department of Health and Human Services Publication No. 84-100.
  - NIOSH. Manual of Analytical Methods, February 1984. U.S. Department of Health and Human Services Publication No. 84-100.
- (7) ASTM. 1990. Annual Book of Standards, Volume 11.03.
- Riggin, R.M. Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air. EPA/600/4-84/041.
- Winberry, W.T. Supplement to U.S. EPA/600/4-84/041: Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air. EPA/600/4-87/006.
- OSHA. Analytical Methods Manual, Second Edition. Part 1, Organic Substances, January 1990. Part 2, Inorganic Substances August 1991.
- Patty, F.A., Industrial Hygiene and Toxicology, Third Edition, John Wiley and Sons, Inc., New York, NY.
- Air Sampling Instruments for Evaluation of Atmospheric Contaminants, Seventh Edition, 1989, American Conference of Governmental Industrial Hygienists, Cincinnati, OH

#### **BIBLIOGRAPHY**

Removal Program Representative Sampling Guidance, Volume 2: Air, Environmental Response Branch, Emergency Response Division, Office of Emergency and Remedial Response, Office of Solid Waste and Emergency Response, U.S. Environmental Protection Agency, April 1992, Interim Final.

### APPENDIX A

### PORTABLE SCREENING DEVICES

Where possible, a datalogger should be used to minimize the length of time required for site personnel to be in a potentially contaminated area. Datalogger cable is available from manufacturers for linear output instruments and some nonlinear output instruments. U.S. EPA ERT/REAC has output cables for organic vapor analyzers (i.e., HNU and OVA), toxic gas analyzers (i.e., monitox) and real-time aerosol monitors (i.e., RAM and miniram).

#### C Total Hydrocarbon Analyzers

Total hydrocarbon analyzers used to detect a variety of volatile organic compounds (VOCs) at hazardous waste sites principally employ either a photoionization detector (PID) or a flame ionization detector (FID). Compounds are ionized by a flame or an ultraviolet - lamp. PIDs depend on the ionization potential of the compounds. PIDs are sensitive to aromatic and olefinic (unsaturated) compounds such as benzene, toluene, styrene, xylenes, and acetylene. Greater selectivity is possible by using lowvoltage lamps. The ionization potential of individual compounds can be found in the NIOSH Pocket Guide to Chemical Hazards. These instruments are not compound-specific and are typically used as screening instruments. FIDs are sensitive to volatile organic vapor compounds such as methane, propanol, benzene and toluene. respond poorly to organic compounds lacking hydrocarbon characteristics.

## C Oxygen and Combustible Gas Indicators

Combustible Gas Indicators (CGIs) provide efficient and reliable methods to test for potentially explosive atmospheres. CGI meters measure the concentration of a flammable vapor or gas in air and present these measurements as a percentage of the lower explosive limit (LEL).

The measurements are temperature-dependent. The

property of the calibration gas determines sensitivity. LELs for individual compounds can be found in the NIOSH Pocket Guide to Chemical Hazards. If readings approach or exceed 10% of the LEL, extreme caution should be exercised in continuing the investigation. If readings approach or exceed 25% LEL, personnel should be withdrawn immediately.

'CGIs typically house an electrochemical sensor to determine the oxygen concentration in ambient air. Normally, air contains approximately 20.9% oxygen by volume. Oxygen measurements are of particular importance for work in enclosed spaces, low-lying areas, or in the vicinity of accidents that have produced heavier-than-air vapors which could displace ambient air. The meters are calibrated for sea level and may indicate a false negative (i.e, O2 content) at higher altitudes. Since the air has been displaced by other substances, these oxygen-deficient areas are also prime locations for taking additional organic vapor and combustible gas measurements. Oxygen-enriched atmospheres increase the potential for fires by their ability to contribute to combustion or to chemically react with flammable compounds and promote autoignition.

#### C Toxic Atmosphere Analyzers

The toxic atmosphere analyzer is a compound-specific instrument, designed and calibrated to identify and quantify a specific compound or class of compounds in either gaseous or vapor form. Cross-sensitivity to air pollutants not of interest may be lead to erroneous results.

U.S. EPA/ERT has the following toxic atmosphere analyzers: carbon monoxide, phosgene, nitrous oxide, hydrogen cyanide, sulfur dioxide, hydrogen sulfide, and chlorine gas.

#### Aerosol/Particulate Monitors

A Real-Time Aerosol/Particulate Monitor (RAM) displays readings for total particulates. The instrument employs a pulse light emitting diode which generates a narrow band emission in conjunction with a photovoltaic cell to detect light scattered from particulates.

The U.S. EPA/ERT uses the RAM when the contaminant of concern is associated with particulates, and when responding to fires involving hazardous materials, to identify plume levels. The instrument is very useful in determining the presence of a plume when The U.S. EPA/ERT it is not visible. typically uses RAMs on tripods to obtain particulate concentrations at the breathing zone level. Personal dataloggers are used with the RAMs to document minimum, average and maximum concentrations. This provides real-time data without requiring those in personal protective equipment to be constantly present in the plume.

## Chemical Detector Tubes (Colorimetric Tubes)

A chemical detector tube is a hollow, tubeshaped, glass body containing one or more layers of chemically impregnated inert material. To use, the fused ends are broken off and a manufacturer-specified volume of air is drawn through the tube with a pump to achieve a given detection limit. The chemicals contained within the packing material undergo a chemical reaction with the airborne pollutant present, producing a color change during the intake of each pump stroke. The concentration of a pollutant is indicated by the length of discoloration on a calibrated scale printed on the detector tube.

#### C Radiation Meters

Radiation meters determine the presence and level of radiation. The meters use a gas or solid ion detection media which becomes ionized when radiation is present. The meters are normally calibrated to one probe. Meters that detect alpha, beta, and gamma radiation are available.

# Gold Film (Hydrogen Sulfide and Mercury Vapor) Monitors

Hydrogen sulfide (H<sub>2</sub>S) and Mercury (Hg) monitors operate on the principle that electric resistivity increases across a gold film as a function of H<sub>2</sub>S and Hg concentration. The monitors provide rapid and relatively low detection limits for H<sub>2</sub>S and Hg in air. After extensive sampling periods or high concentrations of H<sub>2</sub>S and Hg, the gold film must be heated to remove contamination and return the monitor to its original sensitivity.

#### C Infrared Detectors

Infrared detectors such as the Miniature Infrared Analyzer (MIRAN) use infrared (IR) absorption as a function of specific compounds. MIRAN instruments apply to situations where the contaminants are identified but concentrations are not. MIRAN instruments generally require AC power.

# SPECIALIZED ANALYTICAL INSTRUMENTS

The continuous monitors described above provide qualitative measurement of air contaminants. Quantitative measurements in the field can be obtained using more sophisticated instruments, such as portable Gas Chromatographs, to analyze grab samples.

## C Direct Air Sampling Portable Gas Chromatographs (GCs)

Portable GCs use gas chromatography to identify and quantify compounds. The time it takes for a compound to move through a chromatographic column is a function of that specific compound or group of compounds. A trained technician with knowledge of the range of expected concentrations of compounds can utilize a portable GC in the field to analyze grab samples. GCs generally require AC power and shelter to operate. This method is limited by its reliance on a short-term grab sample to be representative of the air quality at a site.

#### Remote Optical Sensing

This technique, also referred to as long-path monitoring, involves open-path transmitting either an infrared or ultraviolet light beam across a long open path and measuring the absorbance at specific wavelengths. The technique is capable of analyzing any preselected organic or inorganic volatile compound that can be resolved from compounds naturally occurring in ambient air. Current projected removal applications include perimeter monitoring during site cleanups and measurement of emission 'source strengths during site assessments.

TAGA Direct Air Sampling Mass Spectrometer/Mass Spectrometer

The Trace Atmospheric Gas Analyzer (TAGA), which is operated by the U.S. EPA/ERT, is capable of real-time detection of preselected organic compounds at low parts-per-billion concentrations. The instrument has been successfully used by the U.S. EPA/ERT for isolating individual emission plumes and tracking those plumes back to their sources.

#### APPENDIX B

## Air Sampling Equipment and Media/Devices

## AIR SAMPLING EQUIPMENT

C High-Volume, Total Suspended Particulate (TSP) Samplers

High-volume TSP samplers collect all suspended particles by drawing air across an 8- by 10-inch glass-quartz filter. The sample rate is adjusted to 40 cubic feet per minute (CFM), or 1134 liters per minute (L/min), and it is held constant by a flow controller over the sample period. The mass of TSPs can be determined by weighing the filter before and after sampling. The composition of the filter varies according to the analytical method and the detection limit required.

PM-10 Samplers

PM-10 samplers collect particulates with a diameter of 10 microns or less from ambient air. Particulates of this size represent the respirable fraction, and thus are of special significance. PM-10 samplers can be highvolume or low-volume. The high-volume sampler operates in the same manner as the TSP sampler at a constant flow rate of 40 CFM; it draws the sample through a special impactor head which collects particulates of 10 microns or less. The particulate is collected on an 8- by 10-inch filter. The lowvolume sampler operates at a rate of approximately 17 L/min. The flow must remain constant through the impactor head to maintain the 10-micron cut-off point. The low-volume PM-10 collects the sample on 37-mm Teflon filters.

C High-Volume PS-1 Samplers

High-volume PS-1 samplers draw a sample through polyurethane foam (PUF) or a combination foam and XAD-2 resin plug, and a glass quartz filter at a rate of 5-10 CFM (144 to 282 L/min). This system is

excellent for measuring low concentrations of semivolatiles, PCBs, pesticides, or chlorinated dioxins in ambient air.

C Area Sampling Pumps

These pumps provide flow-rate ranges of 2-20 L/min and have a telescopic sampling mast with the sampling train. Because of the higher volume, this pump is suitable for sampling low concentrations of airborne contaminants (i.e., asbestos sampling). These pumps are also used for metals, pesticides and PAH sampling which require large sample volumes.

C Personal Sampling Pumps

Personal sampling pumps are reliable portable sampling devices that draw air samples through a number of sampling media including resin tubes, impingers, and filters. Flow rates are usually adjustable from 0.1 to 4 L/min (or 0.01 to .75 L/min with a restrictive orifice) and can remain constant for up to 8 hours on one battery charge or continuously with an AC charger/converter.

Canister Samplers

Evacuated canister sampling systems use the pressure differential between the evacuated canister and ambient pressure to bleed air into the canister. The sample is bled into the canister at a constant rate over the sampling period using a critical orifice, a mechanically compensated regulator, or a mass flow control

device until the canister is near atmospheric pressure.

Pressure canister sampling systems use a pump to push air into the canister. To maintain a higher, more controlled flow, the pump typically controls the pressure differential across a critical orifice at the

inlet of the canister, resulting in a pressurized canister at the completion of sampling.

#### AIR SAMPLING MEDIA/DEVICES

If possible, before employing a specific sampling method, consult the laboratory that will conduct the analyses. Many of the methods can be modified to provide better results or a wider range of results.

#### C Summa<sup>R</sup> Canisters

Summa canisters are highly polished passivated stainless steel cylinders. The Summa polishing process brings chrome and nickel to the surface of the canisters, which results in an inert surface. This surface restricts adsorption or reactions that occur on the canister's inner surface after collection. At the site, the canister is either placed in a sampler to control sample collection rate, or opened to collect a grab sample. Samples can be collected by allowing air to bleed into or be pumped into the canister. U.S. EPA/ERT uses 6-liter Summa canisters for VOC and permanent gas analysis.

#### C Passive Dosimeters

Passive dosimeters are clip-on vapor monitors (samplers) in which the diffused contaminants are absorbed on specially active surfaces. prepared Industrial hygienists commonly use dosimeters to time-weighted obtain averages concentrations of chemical vapors, as they can trap over 130 organic compounds. Selective dosimeters have also been developed for a number of chemicals including formaldehyde, ethylene oxide, hydrogen sulfide, mercury vapor, nitrogen dioxide, sulfur dioxide, and ozone. Dosimeters must be sent to a laboratory for analysis.

#### C Polyurethane Foam (PUF)

PUF is a sorbent used with a glass filter for the collection of semivolatile organic compounds such as pesticides, PCBs, chlorinated dioxins and furans, and PAHs. Fewer artifacts (chemical changes that occur to collected compounds) are produced than with some other solid sorbents. PUF is used with the PS-1 sampler and U.S. EPA Method TO13. PUF can also be used with personal sampling pumps when sampling for PAHs using the Lewis/McCloud method. Breakthrough of the more volatile PCBs and PAHs may occur when using PUF.

## Sampling Bags (Tedlar<sup>R</sup>)

Sampling bags, like canisters, transport air samples to the laboratory for analysis. Samples are generally pumped into the bags, but sometimes a lung system is used, in which a pump creates a vacuum around the bag in a vacuum box. Then the sample flows from a source into the bag. This method is used for VOCs, fixed gases (CO<sub>2</sub>, O<sub>2</sub> and N<sub>2</sub>) and methane.

### C Impingers

An impinger allows an air sample to be bubbled through a solution, which collects a specific contaminant by either chemical reaction or absorption. For long sampling periods, the impinger may need to be kept in an ice bath to prevent the solution from evaporating during sampling. The sample is drawn through the impinger by using a sampling pump or more elaborate sampling trains with multiple impingers.

#### Sorbent Tubes/Cartridges

A variety of sampling media are available in sorbent tubes, which are used primarily for industrial hygiene. A few examples are carbon cartridges, carbon molecular sieves, Tenax tubes and tube containing the XAD-2 polymer. Depending upon the sorbent material, tubes can be analyzed using either a solvent extraction or thermal desorption. The former technique uses standard laboratory equipment and allows for multiple analyses of the same sample. The latter technique requires special, but readily available, laboratory equipment and allows only one analysis per sample. In addition, thermal desorption typically allows for lower detection limits by two or more orders of magnitude. Whenever sorbent tubes are

being used for thermal desorption, they should be certified as "clean" by the laboratory doing the analysis.

#### Thermally Desorbed Media

During thermal desorption, high-temperature gas streams are used to remove the compounds collected on a sorbent medium. The gas stream is injected and often cryofocused into an analytical instrument, such as a GC, for compound analysis:

#### C Tenax Tubes

Tenax tubes are made from commercially available polymer (p-phenylene oxide) packed in glass or stainless steel tubes through which air samples are drawn or sometimes pumped. These tubes are used in U.S. EPA Method TO1 and VOST for volatile nonpolar organic, some polar organic, and some of the more volatile semivolatile organics. Tenax is not appropriate for many of the highly volatile organics (with vapor pressure greater than approximately 200 mm Hg).

#### Carbonized Polymers

The carbonized molecular sieve (CMS), a carbonized polymer, is a commercially available, carbon sorbent packed in stainless-steel sampling tubes through which air samples are drawn or sometimes pumped. These are used in U.S. EPA Method TO2 for highly volatile nonpolar compounds which have low-breakthrough volumes on other sorbents. When high-thermal desorption temperatures are used with CMS, more variability in analysis may occur than with other sorbents.

#### C Mixed Sorbent Tubes

Sorbent tubes can contain two type of sorbents. Combining the advantages of each sorbent into one tube increases the possible types of compounds to be sampled. The combination of two sorbents can also reduce the chance that highly volatile compounds will break through the sorbent media. An example of a mixed sorbent tube is the combination of Tenax and charcoal with a carbonized molecular sieve. A potential problem with mixed sorbent tubes is the breakthrough of a compound from an earlier sorbent to a later sorbent from which it

cannot be desorbed.

#### Solvent-Extracted Media

Solvent-extracted media use the principle of chemical extraction to remove compounds collected on a sorbent media. The chemical solvent is injected into an instrument, such as a GC, for analysis of compounds. Examples of solvent-extracted media follow:

#### Chemically Treated Silica Gel

Silica gel is a sorbent which can be treated with various chemicals. The chemically treated silica gel can then be used to sample for specific compounds in air. Examples include the DNPH-coated silica gel cartridge used with U.S. EPA Method TO11.

#### C XAD-2 Polymers

XAD-2 polymers usually are placed in tubes, custom-packed sandwich-style with polyurethane foam, and prepared for use with U.S. EPA Method TO13 or the semi-VOST method. The polymers are used for the collection of semivolatile polar and nonpolar organic compounds. The compounds collected on the XAD-2 polymer are chemically extracted for analysis.

#### Charcoal Cartridges

Charcoal cartridges, consisting of primary and backup sections, trap compounds by adsorption. Ambient air is drawn through them so that the backup section verifies that breakthrough of the analytes on the first section did not occur, and the sample collection was therefore quantitative. Quantitative sample collection is evident by the presence of target chemicals on the first charcoal section and the absence on the second section. Next, the adsorbed compounds must be eluted, usually with a solvent extraction, and analyzed by GC with a detector, such as a Mass Spectrometer (MS).

#### C Tenax Tubes

Cartridges are used in OSHA and NIOSH methods in a manner similar to charcoal cartridges but typically for less volatile

compounds.

#### Particulate Filters

Particulate filters are used by having a sampling pump pass air through them. The filter collects the particulates present in the air and is then analyzed for particulate mass or chemical or radiological composition. Particulate filters are made from different materials which are described below.

## C Mixed Cellulose Ester (MCE)

MCE is manufactured from mixed esters of cellulose which are a blend of nitro-cellulose and cellulose acetate. MCE filters are used often for particulate sampling.

#### C Glass Fiber

Glass fiber is manufactured from glass fibers without a binder. Particulate filters with glass fiber provide high flow rates, wet strength, and high, solid holding capacity. Generally, the filters are used for gravimetric analysis of particulates.

#### Polyvinyl Chloride

Particulate filters with polyvinyl chloride are resistant to concentrated acids and alkalis. Their low moisture pickup and light tare weight make them ideal for gravimetric analysis.

than 0.01% ash. These filters are used to collect particulates.

#### C Teflon

Teflon is manufactured from polytetrafluorethylene (PTFE). Particulate filters with Teflon are easy to handle and exceptionally durable. Teflon filters are used for metal collection.

#### C Silver

Particulate filters manufactured from pure silver have high collection efficiency and uniform pore size. These filters are used for mercury collection and analysis.

#### C Cellulose

Particulate filters with cellulose contain less



## **SOIL SAMPLING**

SOP#: 2012 DATE: 11/16/94

REV. #: 0.0

#### 1.0 SCOPE AND APPLICATION

The purpose of this standard operating procedure (SOP) is to describe the procedures for the collection of representative soil samples. Analysis of soil samples may determine whether concentrations of specific pollutants exceed established action levels, or if the concentrations of pollutants present a risk to public health, welfare, or the environment.

These are standard (i.e., typically applicable) operating procedures which may be varied or changed as required, dependent upon site conditions, equipment limitations or limitations imposed by the procedure. In all instances, the ultimate procedures employed should be documented and associated with the final report.

Mention of trade names or commercial products does not constitute U.S. Environmental Protection Agency (EPA) endorsement or recommendation for use.

#### 2.0 METHOD SUMMARY

Soil samples may be collected using a variety of methods and equipment. The methods and equipment used are dependent on the depth of the desired sample, the type of sample required (disturbed vs. undisturbed), and the soil type. Near-surface soils may be easily sampled using a spade, trowel, and scoop. Sampling at greater depths may be performed using a hand auger, continuous flight auger, a trier, a split-spoon, or, if required, a backhoe.

## 3.0 SAMPLE PRESERVATION, CONTAINERS, HANDLING, AND STORAGE

Chemical preservation of solids is not generally recommended. Samples should, however, be cooled and protected from sunlight to minimize any potential reaction.

# 4.0 INTERFERENCES AND POTENTIAL PROBLEMS

There are two primary interferences or potential problems associated with soil sampling. These include cross contamination of samples and improper sample collection. Cross contamination problems can be eliminated or minimized through the use of dedicated sampling equipment. If this is not possible or practical, then decontamination of sampling equipment is necessary. Improper sample collection can involve using contaminated equipment, disturbance of the matrix resulting in compaction of the sample or inadequate homogenization of the samples where required, resulting in variable, non-representative results.

## 5.0 EQUIPMENT/APPARATUS

Soil sampling equipment includes the following:

- C Sampling plan
- C Maps/plot plan
- C Safety equipment, as specified in the Health
  - and Safety Plan
- C Survey equipment
- C Tape measure
- C Survey stakes or flags
- Camera and film
- C Stainless steel, plastic, or other appropriate
  - homogenization bucket, bowl or pan
- C Appropriate size sample containers
- C Ziplock plastic bags
- C Logbook
- C Labels
- Chain of Custody records and seals
- C Field data sheets
- Cooler(s)
- C Ice
- C Vermiculite
- C Decontamination supplies/equipment
- Canvas or plastic sheet
- C Spade or shovel

- C Spatula
- C Scoop
- C Plastic or stainless steel spoons
- C Trowel
- Continuous flight (screw) auger
- C Bucket auger
- C Post hole auger
- C Extension rods
- C T-handle
- C Sampling trier
- C Thin wall tube sampler
- C Split spoons
- C Vehimeyer soil sampler outfit
  - Tubes
  - Points
  - Drive head
  - Drop hammer
  - Puller jack and grip
- C Backhoe

## 6.0 REAGENTS

Reagents are not used for the preservation of soil samples. Decontamination solutions are specified in the Sampling Equipment Decontamination SOP and the site specific work plan.

#### 7.0 PROCEDURES

#### 7.1 Preparation

- 1. Determine the extent of the sampling effort, the sampling methods to be employed, and the types and amounts of equipment and supplies required.
- 2. Obtain necessary sampling and monitoring equipment.
- 3. Decontaminate or pre-clean equipment, and ensure that it is in working order.
- 4. Prepare schedules, and coordinate with staff, client, and regulatory agencies, if appropriate.
- 5. Perform a general site survey prior to site entry in accordance with the site specific Health and Safety Plan.
- 6. Use stakes, flagging, or buoys to identify and mark all sampling locations. Specific site

factors, including extent and nature of contaminant should be considered when selecting sample location. If required, the proposed locations may be adjusted based on site access, property boundaries, and surface obstructions. All staked locations will be utility-cleared by the property owner prior to soil sampling.

## 7.2 Sample Collection

## 7.2.1 Surface Soil Samples

Collection of samples from near-surface soil can be accomplished with tools such as spades, shovels, trowels, and scoops. Surface material can be removed to the required depth with this equipment, then a stainless steel or plastic scoop can be used to collect the sample.

This method can be used in most soil types but is limited to sampling near surface areas. Accurate, representative samples can be collected with this procedure depending on the care and precision demonstrated by the sample team member. A stainless steel scoop, lab spoon, or plastic spoon will suffice in most other applications. The use of a flat, pointed mason trowel to cut a block of the desired soil can be helpful when undisturbed profiles are required. Care should be exercised to avoid use of devices plated with chrome or other materials. Plating is particularly common with garden implements such as potting trowels.

The following procedure is used to collect surface soil samples:

- 1. Carefully remove the top layer of soil or debris to the desired sample depth with a precleaned spade.
- Using a pre-cleaned, stainless steel scoop, plastic spoon, or trowel, remove and discard a thin layer of soil from the area which came in contact with the spade.
- 3. If volatile organic analysis is to be performed, transfer the sample directly into an appropriate, labeled sample container with a stainless steel lab spoon, or equivalent and secure the cap tightly. Place the remainder of the sample into a stainless steel, plastic, or

other appropriate homogenization container, and mix thoroughly to obtain a homogenous sample representative of the entire sampling interval. Then, either place the sample into appropriate, labeled containers and secure the caps tightly; or, if composite samples are to be collected, place a sample from another sampling interval or location into the homogenization container and mix thoroughly. When compositing is complete, place the sample into appropriate, labeled containers and secure the caps tightly.

# 7.2.2 Sampling at Depth with Augers and Thin Wall Tube Samplers

This system consists of an auger, or a thin-wall tube sampler, a series of extensions, and a "T" handle (Figure 1, Appendix A). The auger is used to bore a hole to a desired sampling depth, and is then withdrawn. The sample may be collected directly from the auger. If a core sample is to be collected, the auger tip is then replaced with a thin wall tube sampler. The system is then lowered down the borehole, and driven into the soil to the completion depth. The system is withdrawn and the core is collected from the thin wall tube sampler.

Several types of augers are available; these include: bucket type, continuous flight (screw), and post-hole augers. Bucket type augers are better for direct sample recovery since they provide a large volume of sample in a short time. When continuous flight augers are used, the sample can be collected directly from the flights. The continuous flight augers are satisfactory for use when a composite of the complete soil column is desired. Post-hole augers have limited utility for sample collection as they are designed to cut through fibrous, rooted, swampy soil and cannot be used below a depth of three feet.

The following procedure will be used for collecting soil samples with the auger:

- 1. Attach the auger bit to a drill rod extension, and attach the "T" handle to the drill rod.
- 2. Clear the area to be sampled of any surface debris (e.g., twigs, rocks, litter). It may be advisable to remove the first three to six inches of surface soil for an area approximately six inches in radius around the

drilling location.

- 3. Begin augering, periodically removing and depositing accumulated soils onto a plastic sheet spread near the hole. This prevents accidental brushing of loose material back down the borehole when removing the auger or adding drill rods. It also facilitates refilling the hole, and avoids possible contamination of the surrounding area.
- 4. After reaching the desired depth, slowly and carefully remove the auger from boring. When sampling directly from the auger, collect the sample after the auger is removed from the boring and proceed to Step 10.
- 5. Remove auger tip from drill rods and replace with a pre-cleaned thin wall tube sampler. Install the proper cutting tip.
- 6. Carefully lower the tube sampler down the borehole. Gradually force the tube samplerinto soil. Care should be taken to avoid scraping the borehole sides. Avoid hammering the drill rods to facilitate coring as the vibrations may cause the boring walls to collapse.
- Remove the tube sampler, and unscrew the drill rods.
- 8. Remove the cutting tip and the core from the device.
- 9. Discard the top of the core (approximately 1 inch), as this possibly represents material collected before penetration of the layer of concern. Place the remaining core into the appropriate labeled sample container. Sample homogenization is not required.
- 10. If volatile organic analysis is to be performed, transfer the sample into an appropriate, labeled sample container with a stainless steel lab spoon, or equivalent and secure the cap tightly. Place the remainder of the sample into a stainless steel, plastic, or other appropriate homogenization container, and mix thoroughly to obtain a homogenous sample representative of the entire sampling interval. Then, either place the sample into appropriate, labeled containers and secure the

caps tightly; or, if composite samples are to be collected, place a sample from another sampling interval into the homogenization container and mix thoroughly.

When compositing is complete, place the sample into appropriate, labeled containers and secure the caps tightly.

- 11. If another sample is to be collected in the same hole, but at a greater depth, reattach the auger bit to the drill and assembly, and follow steps 3 through 11, making sure to decontaminate the auger and tube sampler between samples.
- 12. Abandon the hole according to applicable State regulations. Generally, shallow holes can simply be backfilled with the removed soil material.

## 7.2.3 Sampling at Depth with a Trier

The system consists of a trier, and a "T" handle. The auger is driven into the soil to be sampled and used to extract a core sample from the appropriate depth.

The following procedure will be used to collect soil samples with a sampling trier:

- 1. Insert the trier (Figure 2, Appendix A) into the material to be sampled at a 0° to 45° angle from horizontal. This orientation minimizes the spillage of sample.
- 2. Rotate the trier once or twice to cut a core of material.
- 3. Slowly withdraw the trier, making sure that the slot is facing upward.
- 4. If volatile organic analysis is to be performed, transfer the sample into an appropriate, labeled sample container with a stainless steel lab spoon, or equivalent and secure the cap tightly. Place the remainder of the sample into a stainless steel, plastic, or other appropriate homogenization container, and mix thoroughly to obtain a homogenous sample representative of the entire sampling interval. Then, either place the sample into appropriate, labeled containers and secure the

caps tightly; or, if composite samples are to be collected, place a sample from another sampling interval into the homogenization container and mix thoroughly. When compositing is complete, place the sample into appropriate, labeled containers and secure the caps tightly.

# 7.2.4 Sampling at Depth with a Split Spoon (Barrel) Sampler

The procedure for split spoon sampling describes the collection and extraction of undisturbed soil cores of 18 or 24 inches in length. A series of consecutive cores may be extracted with a split spoon sampler to give a complete soil column profile, or an auger may be used to drill down to the desired depth for sampling. The split spoon is then driven to its sampling depth through the bottom of the augured hole and the core extracted.

When split spoon sampling is performed to gain geologic information, all work should be performed in accordance with ASTM D 1586-67 (reapproved 1974).

The following procedures will be used for collecting soil samples with a split spoon:

- 1. Assemble the sampler by aligning both sides of barrel and then screwing the drive shoe on the bottom and the head piece on top.
- 2. Place the sampler in a perpendicular position on the sample material.
- 3. Using a well ring, drive the tube. Do not drive past the bottom of the head piece or compression of the sample will result.
- 4. Record in the site logbook or on field data sheets the length of the tube used to penetrate the material being sampled, and the number of blows required to obtain this depth.
- 5. Withdraw the sampler, and open by unscrewing the bit and head and splitting the barrel. The amount of recovery and soil type should be recorded on the boring log. If a split sample is desired, a cleaned, stainless steel knife should be used to divide the tube contents in half, longitudinally. This sampler

is typically available in 2 and 3 1/2 inch diameters. However, in order to obtain the required sample volume, use of a larger barrel may be required.

6. Without disturbing the core, transfer it to appropriate labeled sample container(s) and seal tightly.

#### 7.2.5 Test Pit/Trench Excavation

These relatively large excavations are used to remove sections of soil, when detailed examination of soil characteristics (horizontal, structure, color, etc.) are required. It is the least cost effective sampling method due to the relatively high cost of backhoe operation.

The following procedures will be used for collecting soil samples from test pit/trench excavations:

- 1. Prior to any excavation with a backhoe, it is important to ensure that all sampling locations are clear of utility lines, subsurface pipes and poles (subsurface as well as above surface).
- 2. Using the backhoe, a trench is dug to approximately three feet in width and approximately one foot below the cleared sampling location. Place excavated soils on plastic sheets. Trenches greater than five feet deep must be sloped or protected by a shoring system, as required by OSHA regulations.
- 3. A shovel is used to remove a one to two inch layer of soil from the vertical face of the pit where sampling is to be done.
- 4. Samples are taken using a trowel, scoop, or coring device at the desired intervals. Be sure to scrape the vertical face at the point of sampling to remove any soil that may have fallen from above, and to expose fresh soil for sampling. In many instances, samples can be collected directly from the backhoe bucket.
- 5. If volatile organic analysis is to be performed, transfer the sample into an appropriate, labeled sample container with a

stainless steel lab spoon, or equivalent and secure the cap tightly. Place the remainder of the sample into a stainless steel, plastic, or other appropriate homogenization container, and mix thoroughly to obtain a homogenous sample representative of the entire sampling interval. Then, either place the sample into appropriate, labeled containers and secure the caps tightly; or, if composite samples are to be collected, place a sample from another sampling interval into the homogenization container and mix thoroughly. When compositing is complete, place the sample into appropriate, labeled containers and secure the caps tightly.

6. Abandon the pit or excavation according to applicable state regulations. Generally, shallow excavations can simply be backfilled with the removed soil material.

#### 8.0 CALCULATIONS

This section is not applicable to this SOP.

## 9.0 QUALITY ASSURANCE/ QUALITY CONTROL

There are no specific quality assurance (QA) activities which apply to the implementation of these procedures. However, the following QA procedures apply:

- 1. All data must be documented on field data sheets or within site logbooks.
- 2. All instrumentation must be operated in accordance with operating instructions as supplied by the manufacturer, unless otherwise specified in the work plan. Equipment checkout and calibration activities must occur prior to sampling/operation, and they must be documented.

#### 10.0 DATA VALIDATION

This section is not applicable to this SOP.

#### 11.0 HEALTH AND SAFETY

When working with potentially hazardous materials,

follow U.S. EPA, OHSA and corporate health and safety procedures.

### 12.0 REFERENCES

Mason, B.J., Preparation of Soil Sampling Protocol: Technique and Strategies. 1983 EPA-600/4-83-020.

Barth, D.S. and B.J. Mason, Soil Sampling Quality Assurance User's Guide. 1984 EPA-600/4-84-043.

U.S. EPA. Characterization of Hazardous Waste Sites
- A Methods Manual: Volume II. Available
Sampling Methods, Second Edition. 1984 EPA600/4-84-076.


de Vera, E.R., B.P. Simmons, R.D. Stephen, and D.L. Storm. Samplers and Sampling Procedures for Hazardous Waste Streams. 1980 EPA-600/2-80-018.

ASTM D 1586-67 (reapproved 1974), ASTM Committee on Standards, Philadelphia, PA.

## APPENDIX A


## Figures

FIGURE 1. Sampling Augers



## APPENDIX A (Cont'd)

## Figures



÷			
	•		
·			
	÷	,	
,			
		•	